<u>DEDICATION OF THE WATER MAINS:</u>
THE DEVELOPER DEDICATES THE WATER MAINS TO THE EAST CENTRAL SPECIAL UTILITY DISTRICT UPON COMPLETION BY THE DEVELOPER AND ACCEPTANCE BY THE SAN ANTONIO WATER SYSTEM. THE EAST CENTRAL SPECIAL UTILITY DISTRICT WILL OWN AND MAINTAIN SAID WATER MAINS WHICH ARE LOCATED WITHIN THIS PARTICULAR PLAT.

<u>CPS/ SAWS/ COSA UTILITY NOTES:</u>
1. THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC, GAS, WATER AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICE BOARD (CPS ENERGY) AND SAN ANTONIO WATER SYSTEM (SAWS) - IS HEREBY DEDICATED THE EASEMENTS AND RIGHTS-OF-WAY FOR UTILITY, TRANSMISSION AND DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC AND SERVICE PAGE IN THE ALEAS BESTATE AS THE ASSEMBNT, "OVERHANG EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHANG EASEMENT," "UTILITY EASEMENT," "GAS EASEMENT," "TRANSFORMER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES FOR THE REASONS DESCRIBED ABOVE. CPS ENERGY AND SAWS SHALL ALSO HAVE THE RIGHT TO RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS. TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER SEWER GAS AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE

ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION

THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE TV EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREON. CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY


UNDERGROUND ELECTRIC AND GAS FACILITIES. ROOF OVERHANGS ARE ALLOWED WITHIN FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC AND GAS FACILITIES ARE PROPOSED OR EXISTING WITHIN THOSE FIVE (5) AND TEN (10) FOOT

SURVEYOR NOTES: 1. PROPERTY CORNERS ARE MONUMENTED WITH A CAP OR DISK MARKED SURVEYOR'S NAME" UNLESS NOTED OTHERWISE

2. COORDINATES SHOWN ARE BASED ON THE NORTH AMERICAN DATUM OF 1983 (CORS 2. COORDINATES SHOWN ARE BASED ON THE NORTH AMERICAN DATION OF 1805 (COAS 1996) FROM THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE SOUTH CENTRAL ZONE DISPLAYED IN GRID VALUES DERIVED FROM THE NGS COOPERATIVE CORS

3. DIMENSIONS SHOWN ARE SURFACE.

4. BEARINGS ARE BASED ON THE NORTH AMERICAN DATUM OF 1983 (CORS 1996), FROM THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE SOUTH CENTRAL ZONE



STATE OF TEXAS COUNTY OF BEXAR

HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS, AND DRAINAGE LAYOUT. TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

LICENSED PROFESSIONAL ENGINEER NO. 99254 KFW ENGINEERS & SURVEYING, INC.

STATE OF TEXAS

HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY

21 SEPT

REGISTERED PROFESSIONAL LAND SURVEYOR NO. 5543

KFW SURVEYING, LLC 3421 PAESANOS PKWY, SUITE 101 SAN ANTONIO, TEXAS 78231 PHONE: 210-979-8444 FAX: 210-979-8441

FLOOD PLAIN VERIFICATION NOTE: NO PORTION OF THE FEMA 1% ANNUAL CHANCE (100-YEAR) FLOODPLAIN EXISTS WITHIN THIS PLAT AS VERIFIED BY FEMA MAP PANEL: 48029C0435G, EFFECTIVE SEPTEMBER 29, 2010, FLOODPLAIN INFORMATION IS SUBJECT TO CHANGE AS A

RESIDENTIAL FINISHED FLOOR: RESIDENTIAL FINISHED FLOOR ELEVATIONS MUST BE MINIMUM OF (8) INCHES ABOVE FINAL ADJACENT GRADE. (APPENDIX H. 15.2)

DRAINAGE EASEMENT ENCROACHMENTS:
NO STRUCTURE, FENCES, WALLS OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE
SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENTS, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF TCI, THE DIRECTOR OF PUBLIC WORKS OR THE GENERAL MANAGER OF THE SAN ANTONIO RIVER AUTHORITY. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDING OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS. (APPENDIX H)

CLEAR VISION NOTE:
CLEAR VISION EASEMENTS MUST BE FREE OF VISUAL OBSTRUCTIONS IN ACCORDANCE
WITH THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASSHTO) POLICY ON GEOMETRIC DESIGN OF HIGHWAYS AND STREETS, OR LATEST REVISION THEREOF (35-506(d)(5)).

FIRE FLOW NOTE: THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1,500 GPM AT 25 PSI RESIDUAL PRESSURE TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE RESIDENTIAL DEVELOPMENT. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED PRIOR TO THE BUILDING PERMIT APPROVAL IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHALL.

FIRE NOTE:
INGRESS AND EGRESS SHALL BE PROVIDED BETWEEN ALL ADJACENT LOTS FOR ADEQUATE FIRE DEPARTMENT VEHICLE ACCESS PER THE CITY OF SAN ANTONIO FIRE PREVENTION CODE. ANY CROSS ACCESS SHALL NOT BE BLOCKED NOR MAY THIS NOTE BE REMOVED FROM THE PLAT WITHOUT WRITTEN PERMISSION FROM THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE

<u>TREE NOTE:</u> THIS SUBDIVISION IS SUBJECT TO A MASTER TREE PLAN (A/P#2219163) WHICH THIS SUBDIVISION IS SUBJECT TO A MASTER TREE PLAN (NO #42219105) WHICH REQUIRES COMPLIANCE BY THE OWNERS OF ALL PROPERTY WITHIN THE PLAT BOUNDARY, AND THEIR EMPLOYEES AND CONTRACTORS, AND SHALL BE BINDING ON ALL SUCCESSORS IN TITLE EXCEPT FOR THE OWNERS OF SINGLE-FAMILY RESIDENTIAL LOTS SUBDIVIDED HEREUNDER FOR WHICH CONSTRUCTION OF A STRUCTURE HAS BEEN COMPLETED. THE MASTER TREE PLAN IS ON FILE AT THE CITY OF SAN ANTONIO BEEN COMPLETED. THE MASTER THEE PLANTS ON PILE AT THE CITY OF SAN ANTONIO ARBORISTS OFFICE. NO TREES OR UNDERSTORY SHALL BE REMOVED WITHOUT PRIOF APPROVAL OF THE CITY ARBORISTS OFFICE PER 35-477(h).

COMMON AREA MAINTENANCE NOTE: THE MAINTENANCE OF ALL OPEN SPACE, GREENBELTS, PARKS, TREE SAVE AREAS, INCLUDING LOT 903, BLOCK 13 DRAINAGE EASEMENTS AND EASEMENTS OF ANY NATURE WITHIN THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR THE PROPERTY OWNERS' ASSOCIATION OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR

KEY NOTES

(0.08 AC)(PERMEABLE)

5' WATER EASEMENT

PRIVATE DRAINAGE

T.V. EASEMENT

20' PRIVATE DRAINAGE

EASEMENT (PERMEABLE)

OFF-LOT VARIABLE WIDTH

EASEMENT (PERMEABLE)

③

4

10' ELECTRIC, GAS, TELEPHONE

30' PRIVATE DRAINAGE EASEMENT

10' ELECTRIC, GAS, TELEPHONE, & CABLE

(VOL 20001, PGS 2101-2104 D.P.R.)

2 1' VEHICULAR NON-ACCESS EASEMENT (VOL 20001, PGS 2101-2104 D.P.R.)

(VOL 20001, PGS 324-325 D.P.R.)

10' BUILDING SETBACK LINE

(NOT TO SCALE)

T.V. EASEMENT

14' ELECTRIC, GAS, TELEPHONE, AND

1' VEHICULAR NON-ACCESS EASEMENT

10' ELECTRIC, GAS, TELEPHONE, & CABLE

VOL 20001, PGS 2094-2095 D.P.R.)

(VOL 20001, PGS 2094-2095 D.P.R.)

(VOL 20001, PGS 2094-2095 D.P.R.)

PALOMA SUBDIVISION UNIT 10

(VOL. 20001, PGS 2101-2104, D.P.R.)

LOT 67, 68, 69,

PERMEABLE

-70, 71, 72

(0.11 AC.)

69

1' VEHICULAR NON-ACCESS EASEMENT

10' BUILDING SETBACK LINE

1' VEHICULAR NON-ACCESS EASEMENT

LEGEND

SET 1/2" IRON ROD WITH BLUE CAP

SET 1/2" IRON ROD WITH YELLOW

PROPOSED EASEMENT

MINIMUM FINISHED FLOOR

EXISTING EASEMENT

= PROPOSED CONTOURS

- 970 = EXISTING MAJOR CONTOURS

- CENTERLINE OF ROAD

E.G.T.TV. = ELECTRIC, GAS, TELEPHONE &

O.P.R. = OFFICIAL PUBLIC RECORDS OF

D.P.R. = DEED AND PLAT RECORDS OF

BEXAR COUNTY TEXAS

CARDUCCI DR.

(50' R.O.W.)

196

195

R.O.W. = RIGHT-OF-WAY

N.T.S. = NOT TO SCALE

AC. = ACRE

VOL. = VOLUME

PG. = PAGE

197

60

30

198

- REPLAT AREA

59

SAVANNAH PLACE UNIT 2

LGI HOMES, TEXAS LLC

LOT P-13 & P-5

144.78 ACRES

(PLAT NO. 19-11800321)

58

AREA BEING REPLATED THROUGH

PUBLIC HEARING WITH WRITTEN NOTIFICATION

THE 0.1102 ACRES BEING REPLATED ARE LOTS 67, 68, 69,

70, 71, 72, BLOCK 13, N.C.B. 18225 PALOMA SUBDIVISION

IINIT 10. RECORDED IN VOLUME 20001, PAGES 2101 - 2104

PLAT RECORDS OF BEXAR COUNTY, TEXAS,

N.C.B. = NEW CITY BLOCK

ESMT. = EASEMENT

○ F.I.R. = FOUND 1/2" IRON ROD

(#)

(#)

FF = 527.6

<u>OPEN SPACE NOTE:</u> LOT 903, BLOCK 13 IS DESIGNATED AS AN OPEN SPACE AND AS A COMMON AREA AND DRAINAGE EASEMENT

<u>WASTEWATER EDU NOTE:</u> THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDUS) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE UNDER THE PLAT NUMBER AT THE SAN ANTONIO RIVER AUTHORITY

<u>DETENTION POND NOTE:</u>
STORM WATER DETENTION IS REQUIRED FOR THIS PROPERTY AND IS ACCOUNTED FOR IN AN OFFSITE DETENTION POND LOCATED IN LOT 900, BLOCK 41, N.C.B. 18225, PALOMA SUBDIVISION UNIT 8B, RECORDED IN VOLUME 20001, PAGES 2319-2320 (PLAT #

PLAT NOTES APPLY TO EVERY PAGE OF THIS MULTIPLE PAGE PLAT

23.56'

23.56'

21.68'

23.31'

48.44'

1.65'

23.46'

23.67'

23.46'

9.40

15.66'

15.00'

75.00'

125.00'

14.89'

4.70'

7.84

89°35'38"

7°10'42"

7°10'42"

21.14

9.39'

15.65'

SAN ANTONIO RIVER AUTHORITY NOTE: SAN ANTONIO RIVER AUTHORITY (SARA) IS HEREBY DEDICATED THE EASEMENTS AND RIGHTS-OF-WAY FOR SANITARY SEWER COLLECTION AND TREATMENT FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "SANITARY SEWER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, OPERATING, MAINTAINING, REMOVING AND INSPECTING SANITARY SEWER PIPELINES AND COLLECTION SYSTEMS AND ALL NECESSARY ABOVE-GROUND OR BELOW-GROUND APPURTENANCES. TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LAND, THE RIGHT TO RELOCATE SAID FACILITIES WITHIN SAID EASEMENT AND RIGHT-OF-WAY AND THE RIGHT TO REMOVE FROM SAID LAND ALL TREES AND VEGETATION OR PARTS
THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE FUNCTION OF SAID FACILITIES. IT IS AGREED AND UNDERSTOOD THAT NO BUILDINGS. WITHOUT AN ENCROACHMENT AGREEMENT WITH SARA

1.70'

49.34'

L10

STATE OF TEXAS

RICHARD MOTT

OWNER/DEVELOPER

SAN ANTONIO, TX 78259

Outober 2020

OWNER'S DULY AUTHORIZED AGENT

COUNTY OF BEXAF

COMMISSION AT ITS MEETING OF

REPLATTING OF THIS PROPERTY.

ANY COVENANTS OR RESTRICTIONS

LENNAR HOMES OF TEXAS LAND & CONSTRUCTION LTD.

SWORN AND SUBSCRIBED BEFORE ME THIS THE

. Notary Public, State of Texas

1 601

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS

MY COMMISSION EXPIRES: 6-19-21

L9 48.82' N29°01'49"E

N29°14'17"

S29°47'07"W

THE AREA BEING REPLATTED WERE PREVIOUSLY PLATTED AS LOTS 1

AND 2, BLOCK 12 C.B. 5088, ON PALOMA SUBISIVION UNIT 8A WHICH IS

RECORDED IN VOLUME 20001 PAGES 2094 - 2095 DEED AND PLAT


HEARING WHICH INVOLVED NOTIFICATION ON THE PROPOSED

RECORDS IN BEXAR COUNTY TEXAS. THE SAN ANTONIO PLANNING

I (WE), THE OWNER(S) OF THE PROPERTY SHOWN ON THIS REPLAT

HEREBY CERTIFY THAT THIS REPLAT DOES NOT AMEND OR REMOVE

CURVE LENGTH RADIUS TANGENT DELTA CHORD CHORD BEARING LINE TABLE LINE LENGTH BEARING 15.00' 15.00' 90°00'00" 21.21' S74°47'07"W 50.00' N29°47'07"E 15.00' 15.00' 90°00'00" S15°12'53"E 15.00' 13.23' 82°48'11" 19.84 S71°11'46"W 50.01' N23°55'37" L3 55.30' N21°38'06"E 15.00' 14.75' 89°01'40" 21.03' S22°52'44"E 365.00' 24.25' 7°36'11" 48.40" S25°26'11"W L4 41.23' N29°22'54" 13.76 125.00' 0.82' 0°45'18" S29°24'28"W N29°22'45" 1.65" L6 13.01' S67°23'35"E 15.00' 14.89' N15°25'04"W 89°35'38" 21.14 15.00 90°24'22" L7 11.86' S67°23'35"E 15.11' 21.29' N74°34'56"E



N15°25'04"W

N63°48'14"W

N63°48'14"W

STATE OF TEXAS

THE AREA BEING REPLATTED WERE PREVIOUSLY PLATTED AS LOTS 67, 68, 69, 70, 71, 72, BLOCK 13 N.C.B. 18225, ON PALOMA SUBISIVION UNIT 10 WHICH IS RECORDED IN VOLUME 20001 PAGES 2101 - 2104 968 = EXISTING MINOR CONTOURS DEED AND PLAT RECORDS IN BEXAR COUNTY TEXAS. THE SAN ANTONIO PLANNING COMMISSION AT ITS MEETING OF HELD A PUBLIC HEARING WHICH INVOLVED NOTIFICATION ON THE PROPOSED REPLATTING OF THIS PROPERTY.


> I (WE), THE OWNER(S) OF THE PROPERTY SHOWN ON THIS REPLAT HERÉBY CERTIFY THAT THIS REPLAT DOES NOT AMEND OR REMOVE ANY COVENANTS OR RESTRICTIONS

RICHARD MOTT OWNER/DEVELOPER LENNAR HOMES OF TEXAS LAND & CONSTRUCTION LTD. SAN ANTONIO, TX 78259

OWNER'S DULY AUTHORIZED AGENT

SWORN AND SUBSCRIBED BEFORE ME THIS THE 9 th October 2020

MY COMMISSION EXPIRES: 6-19-21 JOHN ADKINS Notary Public, State of Texa Comm, Expires 06-19-2021 Notary ID 126936805 - REPLAT AREA



Comm Expires 06-19-2021 Notary ID 126936805 100.00 N60°12'53"W 115.00 10 N60°12'54"V 115.00

AREA BEING REPLATED THROUGH PUBLIC HEARING WITH WRITTEN NOTIFICATION

21

THE 0.2496 AC. BEING REPLATTED WAS PLATTED AS LOT 1 AND 2 BLOCK 12 C.B. 5088 PALOMA SUBDIVISION UNIT 8A, RECORDED IN VOLUME 20001 PAGES 2094 - 2095 PLAT RECORDS IN BEXAR COUNTY, TEXAS.

C15 23.56' 15.00' 15.00' 89°59'48" 21.21' \$74°47'13"W

PLAT NUMBER 19-11800450

REPLAT & SUBDIVISION PLAT ESTABLISHING PALOMA SUBDIVISION UNIT 9

BEING A TOTAL 17.86 ACRES OF LAND, INCLUDING 0.2496 OF AN ACRE OF LAND OUT OF PALOMA SUBDIVISION UNIT 8A, LOTS 1 & 2 BLOCK 12 N.C.B. 18225, CITY OF SAN ANTONIO, BEXAR COUNTY, TEXAS. AND ALSO 0.1102 OF AN ACRE OF LAND DESIGNATED AS AN OFF LOT PRIVATE DRAINAGE EASEMENT, AND SITUATED IN THE J.B. HILL SURVEY NO. 103 ABSTRACT 308, AND AS CONVEYED BY DEEDS RECORDED IN DOCUMENT NO. 20180145104, DOCUMENT NO. 20180190166, OFFICIAL PUBLIC RECORDS, AND VOLUME 20001 PAGES 2094 - 2095 PLAT RECORDS OF BEXAR COUNTY, TEXAS.

LENNAR HOMES OF TEXAS LAND & CONSTRUCTION LTD SAN ANTONIO, TX 78259 PHONE: (210) 403-6282

1922 DRY CREEK WAY, STE. 101 ENGINEERS + SURVEYING Phone #: (210) 979-8444 • Fax #: (210) 979-8441

TBPE Firm #: 9513 • TBPLS Firm #: 10122300

STATE OF TEXAS

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS, AND PUBLIC PLACES THEREON SHOWN FOITHE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

RICHARD MOTT OWNER/DEVELOPER LENNAR HOMES OF TEXAS LAND & CONSTRUCTION LTD. 1922 DRY CREEK WAY, SUITE 101

COUNTY OF BEXAF

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED RICHARD MOTT KNOWN TO ME TO BE THE PERSON WHOSE NAME IS
SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND

GIVEN UNDER MY HAND AND SEAL OF OFFICE

STATE OF TEXAS

JOHN ADKINS Notary Public, State of Texas Comm, Expires 06-19-2021 Notary ID 126936805

THE OWNER OF LAND SHOWN ON THIS PLAT. IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS, AND PUBLIC PLACES THEREON SHOWN FOI THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

SHANNON BIRT OWNER/DEVELOPER LGI HOMES - TEXAS LLC THE WOODLANDS, TEXAS 77380

MEGHAN JANE GRACE Notary Public, State of Texas Comm. Expires 12-27-2020 Notary ID 12081891

DATED

STATE OF TEXAS

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED SHANNON BIRT , KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND


PALOMA SUBDIVISION UNIT 9 SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR VARIANCE(S) HAVE BEEN GRANTED.

THIS	_DAY	OF	***************************************	A.D.	20	<u></u> .

SECRETAR

TRAVIS R. ELSETH 99254

PAGE 1 OF 2



SAN ANTONIO, TEXAS 78231 PHONE: 210-979-8444 FAX: 210-979-8441

144.78 ACRES (PLAT NO. 19-11800321)

45>



