

## ATTACHMENT II

### Route Description

This project will install approximately 5,000-feet of new transmission water main from the proposed Turtle Creek No. 3 Pump Station to a tie-in point on Fredericksburg Road which will connect the pipe to an existing 24-inch water main. The pipe will start at the Turtle Creek Pump Station No. 3 located at 4641 Bluffdale Drive. The pipe will head southwest along Bluffdale Drive to the intersection of Fairhaven Street then approximately 400-feet along Fairhaven Street the pipe will head in a southwesterly direction across several properties until it reaches Datapoint Drive. The pipe will cross Datapoint Drive and head in a westerly direction crossing Fredericksburg Road and end at the Medical Center Tank site located at 8311 Fredericksburg Road.

Project Located In: NCB 12830, 13662, 14595