

HISTORIC AND DESIGN REVIEW COMMISSION

August 17, 2016

Agenda Item No: 24

HDRC CASE NO: 2016-318
COMMON NAME: 815 S ST MARYS
ADDRESS: 809 S ST MARYS
LEGAL DESCRIPTION: NCB 738 BLK 1 LOT N IRR 120 OF 1 OR A1,S IRR 51.6 OF N 117 OF 1&2,NE TRI OF 6 OR A7
ZONING: C2 IDZ H
CITY COUNCIL DIST.: 1
DISTRICT: King William Historic District
APPLICANT: Kaliki Mendoza/Southwest Signs
OWNER: Southtown Professional Group
TYPE OF WORK: Signage
REQUEST:

The applicant is requesting a Certificate of Appropriateness for approval to install signage at 811 S St Mary's featuring total of approximately thirteen (13) square feet.

APPLICABLE CITATIONS:

Historic Design Guidelines, Chapter 6, Guidelines for Signage

1. General

A. GENERAL

- i. Number and size*—Each building will be allowed one major and two minor signs. Total requested signage should not exceed 50 square feet.
- ii. New signs*—Select the type of sign to be used based on evidence of historic signs or sign attachment parts along the building storefront where possible. Design signs to respect and respond to the character and/or period of the area in which they are being placed. Signs should identify the tenant without creating visual clutter or distracting from building features and historic districts.
- iii. Scale*—Design signage to be in proportion to the facade, respecting the building's size, scale and mass, height, and rhythms and sizes of window and door openings. Scale signage (in terms of its height and width) to be subordinate to the overall building composition.

B. HISTORIC SIGNS

- i. Preservation*—Preserve historic signs, such as ghost signs or other signs characteristic of the building's or district's period of significance, whenever possible.
- ii. Maintenance*—Repair historic signs and replace historic parts in-kind when deteriorated beyond repair.

C. PLACEMENT AND INSTALLATION

- i. Location*—Place signs where historically located and reuse sign attachment parts where they exist. Do not erect signs above the cornice line or uppermost portion of a facade wall, or where they will disfigure or conceal architectural details, window openings, doors, or other significant details.
- ii. Obstruction of historic features*—Avoid obscuring historic building features such as cornices, gables, porches, balconies, or other decorative elements with new signs.
- iii. Damage*—Avoid irreversible damage caused by installing a sign. For example, mount a sign to the mortar rather than the historic masonry.
- iv. Pedestrian orientation*—Orient signs toward the sidewalk to maintain the pedestrian oriented nature of the historic districts.

D. DESIGN

- i. Inappropriate materials*—Do not use plastic, fiberglass, highly reflective materials that will be difficult to read, or other synthetic materials not historically used in the district.
- ii. Appropriate materials*—Construct signs of durable materials used for signs during the period of the building's construction, such as wood, wrought iron, steel, aluminum, and metal grill work.
- iii. Color*—Limit the number of colors used on a sign to three. Select a dark background with light lettering to make signs more legible.
- iv. Typefaces*—Select letter styles and sizes that complement the overall character of the building façade. Avoid hard-to-read or overly intricate styles

E. LIGHTING

- i. Lighting sources*—Use only indirect or bare-bulb sources that do not produce glare to illuminate signs. All illumination shall be steady and stationary. Internal illumination should not be used.
- ii. Neon lighting*—Incorporate neon lighting as an integral architectural element or artwork appropriate to the site, if used.

F. PROHIBITED SIGNS

i. An abbreviated list of the types of signs prohibited within San Antonio's historic districts and on historic landmarks is provided below. Refer to UDC Section 35-612(j) and Chapter 28 of the Municipal Code for more detailed information on prohibited signs. Billboards, junior billboards, portable signs, and advertising benches. Pole signs. Revolving signs or signs with a kinetic component. Roof mounted signs, except in the case of a contributing sign. Digital and/or LED lighted signs, not to include LED light sources that do not meet the definition of a sign. Moored balloons or other floating signs that are tethered to the ground or to a structure. Any sign which does not identify a business or service within the historic district or historic landmark. Any non-contributing sign which is abandoned or damaged beyond 50 percent of its replacement value, including parts of old or unused signs. Notwithstanding the above, signs designated as a contributing sign or structure by the historic preservation officer shall not be prohibited unless or until such designation is revoked.

G. MULTI-TENANT PROPERTIES

- i. Signage Plan*—Develop a master signage plan or signage guidelines for the total building or property.
- ii. Directory signs*—Group required signage in a single directory sign to minimize visual color and promote a unified appearance

3. Projecting and Wall-Mounted Signs

A. GENERAL

- i. Mounting devices*—Construct sign frames and panels that will be used to be attach signs to the wall of a building of wood, metal, or other durable materials appropriate to the building's period of construction.
- ii. Structural supports*—Utilize sign hooks, expansion bolts, or through bolts with washers on the inside of the wall depending upon the weight and area of the sign, and the condition of the wall to which it is to be attached.
- iii. Appropriate usage*—Limit the use of projecting and wall-mounted signs to building forms that historically used these types of signs, most typically commercial storefronts. To a lesser degree, these signage types may also be appropriate in areas where residential building forms have been adapted for office or retail uses, if sized accordingly.

B. PROJECTING SIGNS

- i. Placement*—Mount projecting signs perpendicularly to a building or column while allowing eight feet of overhead clearance above public walkways.
- ii. Public right-of-way*—Limit the extension of projecting signs from the building facade into the public right-of-way for a maximum distance of eight feet or a distance equal to two-thirds the width of the abutting sidewalk, whichever distance is greater.
- iii. Area*—Projecting signs should be scaled appropriately in response to the building façade and number of tenants.

FINDINGS:

- a. The structure at 809 S St Mary's is commonly known as the King William Professional Building and was constructed circa 1940. It has undergone recent façade modifications which include the installation of two blade signs reading "Brigid" featuring approximately nine square feet and "Francis Bogside" featuring approximately eight square feet. Both signs are constructed of steel and copper and are back lit to produce halo lighting.
- b. The applicant has proposed to install a blade sign reading "Alamo City Cryotherapy" to feature white lexan face to be internally illuminated by white LED lights. The proposed sign will be 24 inches in height and 3' – 4" in

length for an approximately square footage of thirteen (13) sq ft.


- c. Staff finds the overall size of the proposed signage appropriate; however, staff finds that internal illumination in addition to white lexan faces will illuminate the entire sign cabinet, which is not consistent with the Guidelines for Signage 1.E. Staff recommends the applicant incorporate a sign face and lighting method that will produce back lighting or halo lighting.

RECOMMENDATION:

Staff does not recommend approval based on finding b. Staff recommends the applicant incorporate a sign face and lighting method that will produce back lighting or halo lighting.

CASE MANAGER:

Edward Hall



Flex Viewer

Powered by ArcGIS Server

Printed: Aug 08, 2016

The City of San Antonio does not guarantee the accuracy, adequacy, completeness or usefulness of any information. The City does not warrant the completeness, timeliness, or positional, thematic, and attribute accuracy of the GIS data. The GIS data, cartographic products, and associated applications are not legal representations of the depicted data. Information shown on these maps is derived from public records that are constantly undergoing revision. Under no circumstances should GIS-derived products be used for final design purposes. The City provides this information on an "as is" basis without warranty of any kind, express or implied, including but not limited to warranties of merchantability or fitness for a particular purpose, and assumes no responsibility for anyone's use of the information.



Madison St

Turner St

King William Park

Turner St

S Alamo St

Rosario's Mexican Cafe Y Cantina

Turner St

815 South Saint Mary's Street

San Antonio Running Company

King William District CrossFit

B.Link

Madison St

Enterprise Rent-A-Car
S St Mary's St

La Villita Inn

Goodyear Auto Service Center

La Focaccia Italian Grill

S St Mary's St

King William Garden House

S Alamo St

El M...

815 S. ST. MARYS – ALAMO CITY CRYOTHERAPY



809
ALABAMA CITY
COMMUNITY CENTER
210-222-2100

LA OFFICE

CITY OF SAN ANTONIO
NOTICE OF HEARING
CIVIL SERVICE & BENEFIT
REVISION CASE NUMBER

APPLICANT:	<input type="text"/>
POSITION:	<input type="text"/>
INCUMBENT:	<input type="text"/>

TERMS: 100 P.M.
FOR MORE INFORMATION CONTACT
ANN HENNING
CITY HUMAN RESOURCES DEPT. 1000 N. MEADE

City



Brigido

6.6 SQ. FEET



southwestsigns.com
(210) 648-3221 / 800-927-3221

PRESENTATION DRAWING

Project ID# 108030-01 of 01

Client:

Alamo City CryoTherapy

Location:

809 S Saint Marys St
San Antonio, TX 78205

Sales Rep:

Custom

Project Manager: K. Mendoza

Date:

11/16/15

Designer:

DR

Revision:

R1) color options, oval sign 1/6/16 DR

R2) oval sign options 1/13/16 DR

R3) rev. background to lt. gray 4/20/16 DR

R4) add radius sign 5/23/16 DR

R5) Opt2, intern. illum. 7/11/16 DR

R6) rev. structure of sign 7/29/16 DR

Description:

"THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN."




**Primary wires provided by customer.
Sign voltage based upon 120v.**

THIS IS AN ORIGINAL UN-PUBLISHED DRAWING CREATED BY SWS SIGNS. IT IS SUBMITTED FOR YOUR PERSONAL USE IN CONJUNCTION WITH A PROJECT BEING PLANNED FOR YOU BY SWS SIGNS. IT IS NOT TO BE SHOWN TO ANYONE OUTSIDE YOUR ORGANIZATION, NOR IS IT TO BE USED, REPRODUCED, COPIED OR EXHIBITED IN ANY FASHION.


LL Approval:

Customer Approval:



FACE VIEW

SCALE: 1" = 1'-0"



TOP VIEW

SCALE: 1" = 1'-0"

COLOR SPECS

- WHITE
- 281C BLUE / 36 BLUE
- BLACK / 22 BLACK
- 312C BLUE / 57 BLUE

MFG. & INSTALL D/F INTERNALLY ILLUMINATED FLAG MOUNTED BLADE SIGN

FLAT WHITE LEXAN FACES W/ VINYL APPLIED 1ST SURFACE INTERNALLY ILLUMINATED W/ WHITE LEDS
1/2" BLACK RETAINER ON VERTICAL EDGES HELD WITH PAINTED COUNTERSUNK SCREWS OVER 8" DEEP BLACK RETURNS
COVERED TOP & BOTTOM EDGE W/ 1/4" ALUM. CURVED DECORATIVE ACCENTS W/ PAINTED COUNTERSUNK SCREWS

1" SQUARE TUBES INSIDE CABINET WELDED TO 12" X 24" X 1/2" STEEL MOUNTING PLAGE
SATIN BLACK PAINT MOUNTING STRUCTURE

FLAG MOUNTED W/ NON-CORROSIVE HARDWARE BLOCKING AS REQ'D.





815

SINGLE LANE
MUST
TURN RIGHT



815

KING WILLIAM
PROFESSIONAL
BUILDING

809

LAW
OFFICES

