

SUBDIVISION PLAT ESTABLISHING  
CHURCH UNLIMITED

BEING A 10.659 ACRE TRACT OF LAND OUT OF THE WILLIAM BRISBIN SURVEY NO. 89-1/2, ABSTRACT 54, COUNTY BLOCK 4900, LOCATED IN BEXAR COUNTY TEXAS, BEING A PORTION OF THE REMAINDER OF A 660.12 ACRE TRACT CONVEYED TO CHURCH UNLIMITED AS RECORDED IN VOLUME 18639, PAGE 1203, OF THE REAL PROPERTY RECORDS OF BEXAR COUNTY, TEXAS.



**Stantec**

Stantec Consulting Services Inc. TBPE F-6324

70 NE Loop 410 Suite 1100

San Antonio TX

78216-5893

Tel. 210.525.9090

Fax. 210.525.0529

www.stantec.com



0 100' 200'

1" = 100'

STATE OF TEXAS  
COUNTY OF BEXAR

I, MICHAEL CALDWELL AM THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.


THIS THE 13<sup>th</sup> DAY OF June, 2018

Michael Caldwell  
CHURCH UNLIMITED  
MICHAEL CALDWELL

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED MICHAEL CALDWELL KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 13<sup>th</sup> DAY OF June, 2018

Stephanie H. Cardenas  
NOTARY PUBLIC, BEXAR COUNTY, TEXAS




THIS PLAT OF CHURCH UNLIMITED HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR VARIANCE(S) HAVE BEEN GRANTED.

DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ A.D.,

BY: \_\_\_\_\_  
CHAIRMAN

BY: \_\_\_\_\_  
SECRETARY



VICINITY MAP  
NOT TO SCALE  
SAN ANTONIO, TEXAS

LEGEND

- 1/2" IRON ROD FOUND (UNLESS NOTED)
- 1/2" IRON ROD SET
- MONUMENT FOUND
- MONUMENT SET
- ⊙ BENCHMARK
- 920~ EXISTING CONTOURS

B.C.D.R. BEXAR COUNTY DEED RECORDS  
B.C.D.P.R. BEXAR COUNTY DEED PROPERTY RECORDS  
B.C.O.P.R. BEXAR COUNTY OFFICIAL PUBLIC RECORDS  
G.E.T.V. ESM'T GAS, ELECTRIC, TELEPHONE, & TELEVISION EASEMENT  
& CA.T.V. ESM'T ELECTRIC, GAS, TELEPHONE & CABLE TELEVISION EASEMENT  
D.P.R. DEED OF PLAT RECORDS  
C CENTERLINE  
VOL. VOLUME  
P.G. PAGE

PARCEL LINE DATA		
LINE #	BEARING	DISTANCE
L1	S89°44'42"W	180.00'
L2	S0°15'18"E	30.00'
L3	S89°44'42"W	30.00'
L4	N0°15'18"W	10.00'
L5	S89°44'42"W	144.90'
L6	S75°57'40"W	24.00'
L7	N75°37'44"E	14.00'
L8	S76°40'19"W	11.00'
L9	S15°09'58"E	10.00'
L10	N76°41'58"E	11.00'
L11	N77°23'07"E	326.11'

PARCEL LINE DATA		
LINE #	BEARING	DISTANCE
L12	N73°43'59"E	209.69'
L13	N19°52'07"E	31.66'
L14	N73°48'17"E	69.22'
L15	S16°08'20"E	63.62'
L16	S73°27'31"W	472.27'
L17	S16°17'04"E	105.72'
L18	S87°41'53"W	140.23'
L19	N73°00'38"E	81.91'
L20	N16°59'22"W	60.00'
L21	S73°00'38"W	102.77'

SURVEYOR'S NOTES:

- PROPERTY CORNERS ARE MONUMENTED WITH CAP OR DISK MARKED "STANTEC" UNLESS NOTED OTHERWISE.
- BEARINGS AND COORDINATES ARE BASED ON THE NORTH AMERICAN DATUM OF 1983, TEXAS COORDINATE SYSTEM SOUTH CENTRAL ZONE, UTILIZING THE WDS STATEWIDE VRS NETWORK.
- DIMENSIONS SHOWN ARE SURFACE

IMPACT FEE PAYMENT NOTE:

- WATER & WASTEWATER IMPACT FEES WERE NOT PAID AT THE TIME OF PLATTING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO WATER METER SET AND/OR WASTEWATER SERVICE CONNECTION.

TCEQ-EDWARDS AQUIFER RECHARGE ZONE NOTES:

- THIS SUBDIVISION IS WITHIN THE EDWARDS RECHARGE ZONE. DEVELOPMENT WITHIN THIS SUBDIVISION IS SUBJECT TO CHAPTER 34, ARTICLE VI, DIVISION 6 OF THE SAN ANTONIO CITY CODE ENTITLED "AQUIFER RECHARGE ZONE AND WATERSHED PROTECTION," OR LATEST REVISIONS THEREOF. ANY REGULATED ACTIVITY MUST COMPLY WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS RELATING TO DEVELOPMENT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE.
- NO PERSON SHALL COMMENCE THE CONSTRUCTION OF ANY REGULATED ACTIVITY UNTIL AN EDWARDS AQUIFER PROTECTION PLAN (WATER POLLUTION ABATEMENT PLAN" (WPAP)) OR MODIFICATION TO AN APPROVED PLAN AS REQUIRED BY 30 TAC 213.5 OF THE TEXAS ADMINISTRATIVE CODE, OR LATEST REVISION THEREOF, HAS BEEN FILED WITH THE APPROPRIATE REGIONAL TCEQ OFFICE, AND THE APPLICATION HAS BEEN APPROVED BY THE EXECUTIVE DIRECTOR OF THE TCEQ.

GENERAL NOTES:

- NO STRUCTURE, FENCES, WALLS, OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENTS, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF TCI. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDING OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENT AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS.

TxDOT NOTES:

- FOR RESIDENTIAL DEVELOPMENT DIRECTLY ADJACENT TO STATE RIGHT-OF-WAY, THE DEVELOPER SHALL BE RESPONSIBLE FOR ADEQUATE SETBACK AND/OR SOUND ABATEMENT MEASURES FOR FUTURE NOISE MITIGATION.
- MAXIMUM ACCESS POINTS TO STATE HIGHWAY FROM THIS PROPERTY WILL BE REGULATED AS DIRECTED BY "ACCESS MANAGEMENT MANUAL." THIS PROPERTY IS ELIGIBLE FOR A MAXIMUM COMBINED TOTAL OF TWO (2) ACCESS POINTS ALONG US HIGHWAY 281 BASED ON THE OVERALL PLATTED HIGHWAY FRONTAGE OF 769.71'.
- IF SIDEWALKS ARE REQUIRED BY APPROPRIATE CITY ORDINANCE, A SIDEWALK PERMIT MUST BE APPROVED BY TxDOT PRIOR TO CONSTRUCTION WITHIN STATE RIGHT-OF-WAY. LOCATIONS OF SIDEWALKS WITHIN STATE RIGHT-OF-WAY SHALL BE DIRECTED BY TxDOT.

WASTEWATER EDU NOTE:


THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDUS) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE AT THE SAN ANTONIO WATER SYSTEM UNDER THE PLAT NUMBER ISSUED BY THE DEVELOPMENT SERVICES DEPARTMENT.

SAWS HIGH PRESSURE NOTE:

A PORTION OF THE TRACT IS BELOW THE GROUND ELEVATION OF 1215 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT SUCH LOCATIONS, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMERS SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO.

CPS NOTES:

- THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC AND GAS SYSTEM (CITY PUBLIC SERVICE BOARD) IS HEREBY DEDICATED THE EASEMENTS AND RIGHTS-OF-WAY FOR ELECTRIC AND GAS DISTRIBUTION AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT," "GAS EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHANG EASEMENT," "UTILITY EASEMENT," AND "TRANSFORMER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING POLES, HANGING OR BURYING WIRES, CABLES, CONDUITS, PIPELINES OR TRANSFORMERS, EACH WITH ITS NECESSARY APPURTENANCES TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LAND, THE RIGHT TO RELOCATE SAID FACILITIES WITHIN SAID EASEMENT AND RIGHT-OF-WAY AREAS, AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF SAID LINES OR APPURTENANCES THEREON. IT IS AGREED AND UNDERSTOOD THAT NO BUILDINGS, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN SAID EASEMENT AREA.
- ANY CPS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS EQUIPMENT, LOCATED WITHIN SAID EASEMENT, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATION.
- THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED BELOW:




PARCEL CURVE DATA					
CURVE #	LENGTH	RADIUS	DELTA	CHORD LENGTH	BEARING
C1	646.72'	5869.58'	6°18'47"	646.40'	N13° 03' 19.65"W

STATE OF TEXAS  
COUNTY OF BEXAR

I, HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS, AND DRAINAGE LAYOUT.

MARY JANE PHILLIPS, P.E.  
LICENSED PROFESSIONAL ENGINEER  
TEXAS REGISTRATION NO. 102318

DATE



STATE OF TEXAS  
COUNTY OF BEXAR

I HEREBY CERTIFY THAT THIS PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING AND WAS PREPARED FROM AN ACTUAL SURVEY OF THE PROPERTY MADE ON THE GROUND UNDER MY SUPERVISION.

HAL B LANE, III, R.P.L.S.  
REGISTERED PROFESSIONAL LAND SURVEYOR  
TEXAS REGISTRATION NO. 4690

DATE

