

DRAINAGE NOTES:

1. NO STRUCTURE, FENCES, WALLS, OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENT, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT TO INGRESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDED OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND TO MAKE REPAIRS AS NECESSARY.
2. RESIDENTIAL FINISHED FLOOR ELEVATIONS MUST BE A MINIMUM OF EIGHT (8) INCHES ABOVE FINISHED ADJACENT GRADE (SAN ANTONIO UNIFIED DEVELOPMENT CODE SECTION 35-504(E)(5)).
3. THE MAINTENANCE OF ALL PRIVATE STREETS, OPEN SPACE, GREENBELTS, PARKS, DRAINAGE EASEMENTS AND EASEMENTS OF ANY NATURE WITHIN LANDYN LANE SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE LANDYN LANE HOMEOWNERS ASSOCIATION OR THEIR SUCCESSORS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY. TO INCLUDE BUT NOT LIMITED TO: LOT 61, BLK 11626 AND LOT 62, BLK 11626.

WATER AND SANITARY SEWER NOTE:


THE SOLE WATER AND WASTEWATER SERVICE PURVEYOR FOR THE LANDYN LANE SUBDIVISION IS SAN ANTONIO WATER SYSTEM (SAWS).

CITY PUBLIC SERVICE (CPS) NOTES:

1. THE CITY OF SAN ANTONIO AS A PART OF ITS ELECTRIC AND GAS SYSTEM CITY PUBLIC SERVICE BOARD IS HEREBY DELEGATED THE EASEMENTS AND RIGHTS-OF-WAY FOR ELECTRIC AND GAS DISTRIBUTION AND SERVICE FACILITIES. THESE EASEMENTS ARE PLACED AS PUBLIC UTILITIES EASEMENT, "UPRIGHT EASEMENT" AND TRANSVERSE EASEMENT, FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING POLES, HANGING OR BURYING WIRES, CABLES, CONDUITS, PIPES, OR TRANSFORMERS, EACH WITH ITS NECESSARY APPURTENANCES, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LAND, THE RIGHT TO RELOCATE SAID FACILITIES WITHIN SAID EASEMENT AND RIGHT-OF-WAY AREAS, AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF SAID LINES OR APPURTENANCES, WHETHER THE SAME BE OWNED BY THE OWNER OF THE EASEMENT OR BY THE BUILDER.
2. ANY CPS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS EQUIPMENT, LOCATED WITHIN SAID EASEMENT, WILL BE PLACED WITHIN SAID EASEMENT AREAS.
3. THIS PLAT DOES NOT AMEND, ALTER, RELEASE, OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER DRAINAGE, TELEPHONE, CABLE EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHARGES TO THE OWNER OF THE EASEMENT ARE LOW.
4. CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY BY REAR LOT UNDERGROUND ELECTRIC AND GAS FACILITIES.
5. ROOF OVERHANGS ARE ALLOWED WITHIN THE FIVE (5) FOOT WIDE ELECTRIC, GAS, TELEPHONE AND CABLE T.V. EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC, GAS, TELEPHONE AND CABLE T.V. FACILITIES ARE PROPOSED OR EXISTING WITHIN THOSE FIVE (5) FOOT WIDE EASEMENT.



SETBACK NOTE:

SETBACKS IMPOSED ON THIS PLAT ARE AT THE DISCRETION OF THE DEVELOPER OR BEXAR COUNTY AND ARE NOT SUBJECT TO ENFORCEMENT BY THE CITY OF SAN ANTONIO.



AREA BEING REPLATTED THROUGH PUBLIC HEARING WITH WRITTEN NOTIFICATION

THE AREA BEING REPLATTED WAS PREVIOUSLY PLATTED AS LOT 53, BLOCK 1, NEW CITY BLOCK 11626, TUPELO HEIGHTS SUBDIVISION, CITY OF SAN ANTONIO, BEXAR COUNTY, TEXAS RECORDED IN VOLUME 9561, PAGE 12, DEED AND PLAT RECORDS, BEXAR COUNTY, TEXAS.



GENERAL NOTE:

1. FINISHED CONTOURS SHOWN ON THIS MAP ARE FOR GRAPHICAL PURPOSES ONLY. GUTTER ELEVATIONS AND CENTERLINE PAVEMENT ARE NOT REFLECTED ON THIS MAP DUE TO THE SCALE OF THE PLAT.
2. A 5-FOOT WIDE MAINTENANCE EASEMENTS ARE ESTABLISHED WITHIN THE LOTS ADJACENT TO ALL NON-ATTACHED ZERO LOT LINES.
3. LOT OWNER(S) SHALL PROVIDE SHARED COMMON CROSS ACCESS IN ACCORDANCE WITH UDC 35-506(R)(3).

STATE OF TEXAS COUNTY OF BEXAR:

I HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS AND DRAINAGE LAYOUT TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

JUAN G. RODRIGUEZ, P.E.
LICENSED PROFESSIONAL ENGINEER

STATE OF TEXAS
COUNTY OF BEXAR:
I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY HOWLAND ENGINEERING AND SURVEYING COMPANY.

JAMES CORNELAS, R.P.L.S.
REGISTERED PROFESSIONAL LAND SURVEYOR

SURVEYOR'S NOTES:

1. BEARINGS ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, NORTH AMERICAN DATUM OF 1983/93, SOUTH CENTRAL ZONE.
2. ELEVATIONS ARE BASED ON NAVD 88.
3. COORDINATES SHOWN HEREON ARE TEXAS STATE PLANE COORDINATES - SOUTH CENTRAL ZONE, COORDINATES EXPRESSED IN U.S. SURVEY FEET (NAD 83).
4. DISTANCES SHOWN ARE SURFACE DISTANCES IN U.S. SURVEY FEET. THE FACTOR IS 0.9983002895.

WASTEWATER EDU NOTE:

THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDUS) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE AT THE SAN ANTONIO WATER SYSTEM UNDER THE PLAT NUMBER ISSUED BY THE DEVELOPMENT SERVICES DEPARTMENT.

SAWS HIGH PRESSURE NOTE:

A PORTION OF THE TRACT IS BELOW THE GROUND ELEVATION OF 985 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PS. AT ALL SUCH LOCATIONS, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO.

IMPACT FEE PAYMENT DUE NOTE:

WATER AND/OR WASTEWATER IMPACT FEES ARE NOT PAID AT TIME OF PLATTING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO WATER METER SET AND/OR WASTEWATER SERVICE CONNECTION.

FIRE FLOW DEMAND NOTE:


IN AN EFFORT TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE RESIDENTIAL, COMMERCIAL, AND INDUSTRIAL USES, THE SAN ANTONIO FIRE DEPARTMENT SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE PLAT DEMAND OF 1,200 GPM AT 25 PSI RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

PLAT NUMBER: 170592

REPLAT ESTABLISHING

LANDYN LANE SUBDIVISION

BEING A TOTAL OF 2.23 ACRES ESTABLISHING LOT 1 AND LOT 2, BLOCK 1, NEW CITY BLOCK 11626, BEING OUT OF LOT 53, BLOCK 1, NEW CITY BLOCK 11626, TUPELO HEIGHTS SUBDIVISION, SAN ANTONIO, BEXAR COUNTY, TEXAS, ACCORDING TO THE MAP OR PLAT THEREOF, RECORDED IN VOLUME 9561, PAGE 79, DEED AND PLAT RECORDS, BEXAR COUNTY TEXAS.



ISRO ENGINEERING SERVICES, P.L.L.C.
TBPE REGISTRATION NO.: F-14466
12702 TOEPPERWEIN RD, SUITE 266
LIVE OAK, TEXAS 78233
PHONE (210) 793-8136
MOBILE (956) 236-5615
WWW.ISROGROUP-US.COM

HOWLAND
ENGINEERING AND SURVEYING CO.
TBPE FIRM REGISTRATION NO.: F-4097 TBPLS FIRM REGISTRATION NO.: 109406
109406 TBPLS FIRM REGISTRATION NO.: 109406
1531 S. BARTON RD., SUITE 100, SAN ANTONIO, TX 78229-4411
4902 Sinclair Road, San Antonio, TX 78222, P. 210.648.1600
www.howlandcompanies.com

STATE OF TEXAS
COUNTY OF BEXAR:
THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FUTURE AIRPORTS, AIRPORTS, WATERCOURSES, DRAINS, EASEMENTS, AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/DEVELOPER: AAA MEDICAL SOLUTIONS II, LLC
MR. EDWARD DESTEFANO
6127 SAN PEDRO AVENUE, SUITE NO. 2
SAN ANTONIO, TEXAS 78216


STATE OF TEXAS
COUNTY OF BEXAR:
BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED EDWARD DESTEFANO, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 18 DAY OF May, 2018.

BOBBIE L CLERKLEY
Notary ID #128117928
My Commission Expires
December 3, 2021

STATE OF TEXAS
COUNTY OF BEXAR:
THIS PLAT OF LANDYN LANE SUBDIVISION HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, AND IS HEREBY APPROVED BY SUCH COMMISSION.
DATED THIS ____ DAY OF ____ AD. 2018

BY: CHAIRMAN
BY: SECRETARY



SHEET 1 OF 1