HISTORIC AND DESIGN REVIEW COMMISSION

May 06, 2015 Agenda Item No: 22

HDRC CASE NO: 2015-171

COMMON NAME: Thespian Island - Donaldson at Kampmann

ZONING: UZROW

CITY COUNCIL DIST.: 7

DISTRICT: Monticello Park Historic District

APPLICANT: David Pulido

OWNER: City of San Antonio

TYPE OF WORK: Thespian Island improvements

REOUEST:

The applicant is requesting final approval for the following intersection improvements at the median known as Thespian Island:

Item 1:Wilson Blvd – between Donaldson and Club/Thomas Jefferson

- 1. Reconstruct the curb and 4 foot sidewalks (west side) & ADA compliant ramps.
- 2. Incidental driveway reconstruction.
- 3. Mill and Overlay.
- 4. Add grass to the median.

Item 2: Thespian Island

- 5. Widen the existing Island at Kampmann to provide dedicated right-turn lane to Donaldson while keeping the original island shape intact
- 6. Construct a 5 foot bike lane.
- 7. Construct a 10 foot crossing to the Jefferson High School campus.

APPLICABLE CITATIONS:

UDC Section 35-646 – Construction in Public Rights-of-Way.

- (a) **General Provisions.** All construction in the public right-of-way shall conform to all city codes. In considering an application, the historic and design review commission shall be guided by the following:
 - (1) **Sidewalk Zones.** Pedestrian movement should be pleasant, allowing for store browsing, comfortable transit waiting and easy accessibility for disabled people. Where possible, sidewalks should at least five (5) feet in width. Existing sidewalks should not be narrowed when replaced.
 - (2) **Sidewalk Paving and Surfaces.** Materials should complement stylistic differences of individual buildings, particularly when related to historic buildings.
 - A. **Materials.** Materials should be chosen for beauty, strength, longevity, easy maintenance and traction when dry or wet.
 - B.Color and Texture. To ensure the safety of pedestrians, all changes in surfaces should be defined by contrasting color, texture or materials.

(4) **Streetscape Landscaping.** Landscaping, particularly streets trees, are an important addition to the streetscape because of the hot Texas climate. Appropriate application along sidewalks strengthens the visual quality of public streets. Careful selection of plant materials, using native and low-water use plants, is recommended.

FINDINGS:

- a. Thespian Island is a street median located between Kampmann and Donaldson Ave. The median is located within the Monticello Park Local Historic District as well as the Thomas Jefferson High School National Register District.
- b. The proposed improvements around the Thespian Island and along Wilson Boulevard at Thomas Jefferson High School will increase pedestrian and vehicular safety, benefit the accessibility of the area, and will create an

- aesthetically pleasing public-right-of-way that will complement the existing character of the area.
- c. The Texas Historical Commission has reviewed the project and has noted that the proposed improvements will have no adverse effect on the historic Jefferson High School.
- d. The proposed street improvements for Item 1 and 2 are consistent with the UDC Section 35-646-1-4.

RECOMMENDATION:

Staff recommends approval of items 1 & 2, with the stipulation that the proposed concrete mixture match the color of the existing concrete condition.

CASE MANAGER:

Alyson Smith





Thespian Island

Printed:Apr 28, 2015

The City of San Antonio does not guarantee the accuracy, adequacy, completeness or usefulness of any information. The City does not warrant the completeness, timeliness, or positional, thematic, and attribute accuracy of the GIS data. The GIS data, cartographic products, and associated applications are not legal representations of the depicted data. Information shown on these maps is derived from public records that are constantly undergoing revision. Under no circumstances should GIS-derived products be used for final design purposes. The City provides this information on an "as is" basis without warranty of any kind, express or implied, including but not limited to warranties of merchantability or fitness for a particular purpose, and assumes no responsibility for anyone's use of the information.










CITY OF SAN ANTONIO

DEPARTMENT OF TRANSPORATION & CAPITAL IMPROVEMENTS WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)



ICI

PROJECT STATIONING:

WILSON BLVD. - STA 0+58.85 - 12+40.82

CITY OF SAN ANTONIO
TRANSPORTATION & CAPITAL IMPROVEMENTS

OUR MISSION: TOGETHER, DEDICATED TO OUR COMMUNITY... BUILDING A GREAT SAN ANTONIO

TDLR INSPECTION REQUIRED TDLR NO. <u>EABPRJB5803033</u>




100% SUBMITTAL

Sheet 1 of 90



INDEX OF DRAWINGS

					
SHEET No.	Sheet Title	SHEET N	o. Sheet Title	SHEET	No. Sheet Title
	GENERAL	37	SOUTHWEST CORNER OF WILSON BLVD. AND MEREDITH DR.		TRAFFIC SIGNAL DETAILS
1	TITLE SHEET	38	NORTHWEST CORNER OF WILSON BLVD. AND MEREDITH DR.	74	BICYCLE LANE PAVEMENT MARKING
2	INDEX TO PLANS	39	SOUTHWEST CORNER OF WILSON BLVD. AND ALEXANDER HAMILTON DR.	75	GENERAL NOTES AND GROUND SIGN MOUNTING
3	OVERALL PROJECT LAYOUT	40	NORTHWEST CORNER OF WILSON BLVD. AND ALEXANDER HAMILTON DR.	76	D3 STREET NAME SIGN AND SIGN MOUNTING
4	HORIZONTAL ALIGNMENTS AND VERTICAL CONTROL	41	SOUTHWEST CORNER OF WILSON BLVD. AND THOMAS JEFFERSON DR.	77	GROUND MOUNTED SIGN SIZES
5	WILSON BLVD. PRIMARY AND SECONDARY CONTROL	42	WHEELCHAIR RAMP THESPIAN ISLAND DETAIL 1 OF 1	78	METRO STREET NAME SIGN AND SIGN PLACEMENT
6	THESPIAN ISLAND PRIMARY AND SECONDARY CONTROL		ROADWAY DETAILS	79	LEFT TURN ONLY AND ARROW SPACING WORKSHEET
7	TYPICAL STREET SECTIONS AND DETAILS	43	MISCELLANEOUS CONSTRUCTION STANDARDS I	80	LEFT TURN LANE & RIGHT TURN LANE WORKSHEET
8	CITY OF SAN ANTONIO GENERAL NOTES	44	MISCELLANEOUS CONSTRUCTION STANDARDS II	81	STANDARD PAVEMENT MARKINGS (WORDS)
9	SUPPLEMENTAL GENERAL NOTES	45	WHEELCHAIR RAMP STANDARD	82	STANDARD PAVEMENT MARKINGS (ARROW)
10	SUMMARY OF QUANTITIES	46	CONCRETE DRIVEWAY STANDARDS		EXISTING CONDITIONS AND UTILITIES
11	SEQUENCE OF WORK 1 OF 2	47	CONCRETE BUS STOP PAD	83	WILSON BLVD. PLAN VIEW OF EXISTING CONDITIONS (1 OF 6)
12	SEQUENCE OF WORK 2 OF 2	48	TYPICAL CROSSWALK DETAILS	84	WILSON BLVD. PLAN VIEW OF EXISTING CONDITIONS (2 OF 6)
	TRAFFIC CONTROL PLAN		STREET CROSS SECTION	85	WILSON BLVD. PLAN VIEW OF EXISTING CONDITIONS (3 OF 6)
13	TRAFFIC CONTROL PLAN TYPICAL SECTIONS	49	WILSON STREET CROSS SECTION STA. 1+00 TO STA. 2+00	86	WILSON BLVD. PLAN VIEW OF EXISTING CONDITIONS (4 OF 6)
14	TRAFFIC CONTROL PLAN PHASE I (1 OF 2)	50	WILSON STREET CROSS SECTION STA. 2+50 TO STA. 3+50	87	WILSON BLVD. PLAN VIEW OF EXISTING CONDITIONS 5 OF 6)
15	TRAFFIC CONTROL PLAN PHASE I (2 OF 2)	51	WILSON STREET CROSS SECTION STA. 4+00 TO STA. 5+00	88	WILSON BLVD. PLAN VIEW OF EXISTING CONDITIONS (6 OF 6)
16	TRAFFIC CONTROL PLAN PHASE II (1 OF 2)	52	WILSON STREET CROSS SECTION STA. 5+50 TO STA. 6+50	89	THESPIAN ISLAND PLAN VIEW OF EXISTING CONDITIONS (1 OF 2)
17	TRAFFIC CONTROL PLAN PHASE II (2 OF 2)	53	WILSON STREET CROSS SECTION STA. 7+00 TO STA. 8+00	90	THESPIAN ISLAND PLAN VIEW OF EXISTING CONDITIONS (2 OF 2)
ง 18	TRAFFIC CONTROL PLAN PHASE III (1 OF 2)	54	WILSON STREET CROSS SECTION STA. 8+50 TO STA. 9+50	90	THEST WIN ISBURD I BUN VIET OF EXISTING GONDINGING (2 of 2)
19	TRAFFIC CONTROL PLAN PHASE III (2 OF 2)	55	WILSON STREET CROSS SECTION STA. 10+00 TO STA. 11+00		
i i	TRAFFIC CONTROL STANDARDS	56	WILSON STREET CROSS SECTION STA. 11+50 TO STA. 12+40.82 SWPPP		
20	BARRICADE AND CONSTRUCTION STANDARDS (1 OF 4)	57	ISSUES AND COMMITMENTS EPIC		
21	BARRICADE AND CONSTRUCTION STANDARDS (2 OF 4)	58	STORM WATER POLLUTION PREVENTION PLAN (SWP3) NARRATIVE SHEET	1 OF 2	
22	BARRICADE AND CONSTRUCTION STANDARDS (3 OF 4)	59	STORM WATER POLLUTION PREVENTION PLAN (SWP3) NARRATIVE SHEET		
23	BARRICADE AND CONSTRUCTION STANDARDS (4 OF 4)	60	STORM WATER POLLUTION GENERAL NOTES	2 01 2	TE OF TELL
000	STREET PLAN AND PROFILE	61	S.W.P.P.P. PLAN (WILSON BLVD.)		5 5 70
24	OVERALL PAVEMENT OVERLAY	62	S.W.P.P.P. PLAN (THESPIAN ISLAND)		
25	DRIVEWAY SUMMARY	63	S.W.P.P.P. STANDARDS (1 OF 2)		CHARLES GRADY KOEHL
26	WILSON BLVD. STA. 0+58.85 TO STA. 3+00.00		S.W.P.P.P. STANDARDS (2 OF 2)		83945 ./⊄
27	WILSON BLVD. STA. 3+00.00 TO STA. 5+00.00	64			
28	WILSON BLVD. STA. 5+00.00 TO STA. 7+00.00		TREE PROTECTION		
29	WILSON BLVD. STA. 7+00.00 TO STA. 9+00.00	65	TREE PRESERVATION PLAN		- sures
30	WILSON BLVD. STA. 9+00.00 TO STA. 11+00.00	66	TREE PRESERVATION DEATILS (1 OF 4)		3-3-2015
31	WILSON BLVD. STA. 11+00.00 TO STA. 12+40.82	67	TREE PRESERVATION DEATILS (2 OF 4)		JONES & CARTER, INC.
32	THESPIAN ISLAND PLAN VIEW (1 OF 2)	68	TREE PRESERVATION DEATILS (3 OF 4)		Texas Board of Professional Engineers Registration No. F-439 1000 CENTRAL PARKWAY NORTH SUITE 100 — SAN ANTONIO, TEXAS 78232
33	THESPIAN ISLAND PLAN VIEW (2 OF 2)	69	TREE PRESERVATION DEATILS (4 OF 4)		PHONE: (210) 494-5511 FAX: (210) 494-5519 www.jonescarter.com
34	STREET CROSS SECTIONS DETAILS FOR THESPIAN ISLAND		TRAFFIC PAVEMENT MARKING AND SIGNAGE PLAN		CITY OF SAN ANTONIO TRANSPORTATION & CAPITAL IMPROVEMENTS
35	VIA BUS FOUNDATIONS DETAILS	70	PAVEMENT MARKING AND SIGNAGE PLAN (1 OF 2)		WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)
26 2	WHEELCHAIR RAMP DETAILS	71	PAVEMENT MARKING AND SIGNAGE PLAN (2 OF 2)		INDEX TO PLANS
36	NORTHWEST CORNER OF WILSON BLVD. AND DONALDSON ,	72	PAVEMENT MARKING AND SIGNAGE PLAN THESPIAN ISLAND (1 OF 2)		
© 2015 Jones & Carter,	Inc.	73	PAVEMENT MARKING AND SIGNAGE PLAN THESPIAN ISLAND (2 OF 2)		100 % SUBMITTAL PROJECT NO. 40-00322 DATE: 03/03/2015



 Station
 Northing
 Easting
 Bearing
 Distance

 0+58.85
 13716506.06
 2114715.69

N 06°26'49" E 1181.97' 12+40.82 13717680.56 2114848.41

HORIZONTAL ALIGNMENT: THESPIAN ISLAND

Station Northing Easting Bearing Distance

1+00.000 13716465.547 2115617.898 N 06'27'04" E 29.412'

1+29.412 13716494.773 2115621.203 PC

Radius: 13716487.694 2115683.804 Radius Length: 63.000'

Pl: 13716530.457 2115625.238 1+65.324 Tangent: 35.912' Arc Len: 65.279' Delta: 59°22'06" Right Degree: 90°56'44"

Chord Len: 62.398' Chord Brg: N 36'08'07" E
Radial-In: S 83'32'56" E Radial-Out: S 24'10'50" E

Tangential—In Tangential—Out 1+94.691 13716545.167 2115657.998 PT

N 65°49'10" E 34.761'

2+29.452 13716559.405 2115689.709 Deflection: 02'18'48" Left

N 63*30'22" E 240.355' 4+69.807 13716666.628 2115904.822

T.B.M. "PK" NAIL (STAMPED "JONES & CARTER" - POINT NO. 1901) SET IN THE SIDEWALK AT THE SOUTHWEST CORNER OF DONALDSON AVE. AND

WILSON BLVD. (STA. 1+58.52 35.77' RT.) NORTHING = 13,716,601.47

EASTING = 2,114,759.00 ELEVATION = 713.09 (NAVD '88 DATUM)

BASED ON GLOBAL POSITIONING SYSTEM (GPS)

T.B.M. "PK" NAIL (STAMPED "JONES & CARTER" — POINT NO. 1902) SET IN THE SIDEWALK AT THE SOUTHWEST CORNER OF ALEXANDER HAMILTON DR. AND WILSON BLVD. (STA. 7+78.78 32.35' RT.)

NORTHING = 13,717,218.19 EASTING = 2,114,825.25

ELEVATION = 727.04 (NAVD '88 DATUM)

BASED ON GLOBAL POSITIONING SYSTEM (GPS)

T.B.M. "PK" NAIL (STAMPED "JONES & CARTER" — POINT NO. 1903) SET IN THE SIDEWALK AT THE SOUTHWEST CORNER OF THOMAS JEFFERSON DR. AND WILSON BLVD. (STA. 11+37.54 32.45' RT.)

NORTHING = 13,717,574.69 EASTING = 2,114,865.65

ELEVATION = 734.24 (NAVD '88 DATUM)
BASED ON GLOBAL POSITIONING SYSTEM (GPS)



JONES&CARTER, TRE.

Teus Board of Professional Engineers Registration No. F-439
1000 CENTRAL PARKWAY NORTH SUITE 100 – SAN ANTONIO, TEXAS 78232
PHONE: (210) 494–5511 FAX: (210) 494–5519 www.jonescarter.com


CITY OF SAN ANTONIO

WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)

HORIZONTAL ALIGNMENTS
AND VERTICAL CONTROL


100_% SUBMITTAL PROJECT NO. 40-00322 DATE: 03/03/2015
DRWN BY: DSGN BY: CHKD BY: SHT NO. 4 0F 90





NOTES:

- 1. THE COORDINATES SHOWN HEREON ARE TEXAS STATE PLANE COORDINATE SYSTEM GRID, SOUTH CENTRAL ZONE 4204 (NAD'83), AS DETERMINED BY GLOBAL POSITIONING SYSTEM (GPS) WITH THE NATIONAL GEODETIC SURVEY (NGS) OPUS POST PROCESSING.
- ALL ELEVATIONS SHOWN HEREON ARE TIED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD'88) BASED ON NGS OPUS POST PROCESSING OF GPS DATA. THE NEAREST PUBLISHED NGS VERTICAL CONTROL MONUMENT IS "AY1917 SAN ANTONIO JEFFERSON HS DOME".



LEGEND



LOT 21, BLOCK 8 JEFFERSON HIGH SCHOOL SUBDIVISION VOL.9523, PG.176 BCDPR

JEFFERSON MANOR SUBDIVISION

"PK" NAIL SET IN CONCRETE SIDEWALK (STAMPED "JONES & CARTER"-"1908") NORTH: 13,718,042.10 EAST: 2,114,907.16 ELEV: 740.05



JONES&CARTER, INC.


1000 CENTRAL PARKWAY NORTH SUITE 100 - SAN ANTONIO, TEXAS 78232
PHONE: (210) 494-5511 FAX: (210) 494-5519 www.jonescarter.com

CITY OF SAN ANTONIO TRANSPORTATION & CAPITAL IMPROVEMENTS


WILSON BLVD. (CLUB-DONALDSON) THESPIAN ISLAND

WILSON BLVD. PRIMARY AND SECONDARY CONTROL

100 % SUBMITTAL PROJECT NO. 40-00322



DSGN BY:



GENERAL NOTES

- ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS FOR CONSTRUCTION JUNE 2008, OR LATEST.
- NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS, BUT NOT INCLUDED IN THE BID PROPOSAL THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED IN THE PAY ITEM TO WHICH IT RELATES.
- THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE DELIVERY OF MAIL BY THE U.S. POSTAL
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION ANY DAMAGE DONE TO EXISTING FENCES, CONCRETE ISLANDS, STREET PAVING, CURBS, SHRUBS, BUSHES OR DRIVEWAYS. (NO SEPARATE PAY ITEM).
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL SIGNS AND BARRICADES ARE PROPERLY INSTALLED AND MAINTAINED ALL LOCATIONS AND DISTANCES WILL BE DECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". THE CITY'S CONSTRUCTION INSPECTOR AND TRAFFIC ENGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECTOR AND TRAFFIC ENGINS. IF, IN THE OPINION OF THE TRAFFIC ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR, THE BARRICADES AND SIGNS DO NOT CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT THE GENERAL PUBLIC, THE CONSTRUCTION INSPECTIOR SHALL HAVE THE OPTION TO STOP OPERATIONS UNTIL SUCH TIME AS THE CONDITIONS ARE CORRECTED.
- 6. IF THE NEED ARISES, ADDITIONAL BARRICADES AND DIRECTIONAL DEVICES MAY BE ORDERED BY THE TRAFFIC ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.171 C.P.S. MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
- CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY FOUR (24) HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES TO SCHEDULE FOR DENSITY TEST AS REQUIRED.

207-8048

207-7720 /207-7765

1-800-344-8377

- CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES, MARKS, ETC. IF ANY ARE DESTROYED ON REMOVED BY THE CONTRACTOR ON HIS EMPLOYEES, THEY SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 10. CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO DETERMINE THE LOCATION OF EXISTING UTILITIES. CONTRACTOR SHALL NOTIFY THE FOLLOWING AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO EXCAVATION OPERATION: SAN ANTONIO WATER SYSTEM (SAWS) 233-201: 233-2010

BEXAR METROPOLITAN WATER DISTRICT (BEXAR MET) 354-6538 /357-5741 COSA DRAINAGE COSA SIGNAL OPERATIONS

TEXAS STATE WIDE ONE CALL LOCATOR

- CITY PUBLIC SERVICE ENERGY - TIME WARNER

- AT&T

- MCI

- 11. THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM AVAILABLE RECORDS AND ARE NOT GUARANTEED, BUT SHALL BE INVESTIGATED AND VERIFIED BY THE CONTRACTOR SHEFORE STARTING WORK. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGE TO AND FOR THE MAINTENANCE AND PROTECTION OF THE EXISTING UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS, LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE REPERSON BY EXPENSE OF THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE SHALL BE RESPONSIBLE FOR PROTECTION OF SAME DURING CONSTRUCTION.
- 12. ALL WASTE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE HIS SOLE REPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE PROJECT. NO WASTE MATE-RIAL SHALL BE PLACED IN EXISTING LOWS THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING ARTIFICIAL OR NATURAL DRAINAGE
- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.
- 14. THE CONTRACTOR SHALL NAINTAIN ALL ADJOINING STREETS AND TRAVELED ROUTES FREE FROM SPILLED AND /OR TRACKED CONSTRUCTION MATERIALS AND /OR DEBRIS.
- 15. IF THE CONTRACTOR ENCOUNTERS ANY ARCHAEOLOGICAL DEPOSITS DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR MUST STOP EXCAVATION IMMEDIATELY, CONTACT THE CITY INSPECTOR, AND CALL THE CITY HISTORIC PRESERVATION OFFICE AT 207-7306 OR 207-3327 FOR AN ARCHAEOLOGICAL INVESTIGATION, THE CONTRACTOR CANNOT BEGIN EXCAVATION AGAIN WITHOUT WRITTEN PERMISSION FROM THE CITY.

WITHOUT WRITTEN PERMISSION FROM THE CITY.

IF MORE THAN THREE (3) DAYS ARE REQUIRED FOR INVESTIGATION (NOT INCLUDING HOLIDAY AND WEEKENDS) AND IF THE CONTRACTOR IS UNABLE TO WORK IN OTHER AREAS, THEN THE CONTRACTOR WILL BE ALLOWED TO NEGOTIATE FOR ADDITIONAL CONSTRUCTION TIME UPON WRITTEN REQUEST WITHIN TEN (10) DAYS AFTER THE FIRST NOTICE TO THE CITY OF ARCHAEOLOGICAL INVESTIGATION FOR EACH EVENT.

IF THE TIME REQUIRED FOR INVESTIGATION IS LESS THAN OR EQUAL TO THREE (3) DAYS FOR EACH EVENT, CONTRACT DURATION WILL NOT BE EXTENDED.

16. IF SUSPECTED CONTAMINATION IS ENCOUNTERED DURING CONSTRUCTION OPERATIONS, C.O.S.A. SHALL BE NOTIFIED IMMEDIATELY WHEN CONTAMINATED SOILS AND /OR GROUNDWATER ARE ENCOUNTERED AT LOCATIONS NOT IDENTIFIED IN THE PLANS. THE NOTIFICATION SHOULD ENCOUNTERED AT LOCATIONS NOT IDENTIFIED IN THE PLANS. THE NOTHIGATION SHOULD INCLUDE THE STATION NUMBER, TYPE OF CONTAMINATION AND MEASURES TAKEN TO CONTAIN THE CONTAMINATED MEDIA AND PREVENT PUBLIC ACCESS. THE CONTAMINATED SOIL AND /OR GROUNDWATER SHALL NOT BE REMOVED FROM THE LOCATION WITHOUT PRIOR C.O.S.A. APPROVAL.

THE CONTRACTOR MUST STOP THE EXCAVATION IMMEDIATELY AND CONTACT THE C.O.S.A. INSPECTOR. THE CONTRACTOR CANNOT BEGIN EXCAVATION ACTIVITIES WITHOUT WRITTEN PERMISSION FROM THE CITY.

17. CONTRACTOR IS TO INCLUDE A MAILBOX POST BLOCKOUT FOR VACANT LOTS AND ALL RESIDENCES WHICH DO NOT HAVE MAILBOXES AT THE CURB. BLOCKOUTS ARE PROVIDED FOR FUTURE USE BY THE POST OFFICE. 18. CONTRACTOR SHALL NOT REMOVE OR ADJUST ANY VIA FACILITIES. THE CONTRACTOR MUST CONTACT VIA FOURTEEN DAYS PRIOR, FOR THE REMOVAL OF BENCHES, STOP POLES OR ANY OTHER VIA FACILITIES THAT MAY BE PRESENT. PLEASE PROVIDE THIRTY DAYS PRIOR NOTICE FOR SHELTER REMOVAL (TELEPHONE NOS: (210) 362-2155 OR (210) 362-2096), THE CONTRACTOR WILL BE LIABLE FOR ANY DAMAGES TO VIA FACILITIES NOT REMOVED BY VIA. THE CON-TRACTOR IS REQUIRED TO REPLACE ALL FLATWORK REMOVED OR DAMAGED IN THE COURSE OF EXECUTING THE CONTRACT UNLESS OTHERWISE NOTED BY VIA. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING VIA FACILITIES IF ADJACENT TO WORK AREA.

TREE PROTECTION AND PRESERVATION GENERAL NOTES

- NO UTILITY OR STREET EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED.
- TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION. DURING CONSTRUCTION ACTIVITY, AT LEAST A SIX-INCH LAYER OF COARSE MULCH SHALL BE PLACED AND MAINTAINED OVER THE ROOT PROTECTION ZONE (NO SEPARATE PAY ITEM).
- 3. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROUBLING WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR FOR GUIDANCE.
- ROOTS WILL BE CUT WITH A ROCK SAW OR BY HAND, NOT BY AN EXCAVATOR OR OTHER ROAD CONSTRUCTION EQUIPMENT.
- ALL CURB AND SIDEWALK WORK SHALL USE ALTERNATIVE CONSTRUCTION METHODS TO MINIMIZE EXTENSIVE ROOT DAMAGE TO TREES (REFER TO DETAILS).
- 6. EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS WITH SOIL, MULCH, OR WET BURLAP.
- NO EQUIPMENT, VEHICLES OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY TREE NEAR THE PROJECT. ROOT PROTECTION ZONE IS 1 FOOT OF RADIUS PER INCH OF TREES DIAMETER, a 10-INCH DIAMETER TREE WOULD HAVE A 10 FOOT RADIUS ROOT PROTECTION ZONE AROUND THE TREE. ROOTS OR BRANCHES IN CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. OAK WOUNDS SHALL BE PAINTED OVER WITHIN 30 MINUTES TO PREVENT
- SAPLINGS, SHRUBS OR BUSHES TO BE CLEARED FROM THE PROTECTED ROOT ZONE AREA OF A LARGE TREE SHALL BE REMOVED BY HAND AS DESIGNATED BY THE INSPECTOR.
- 9 NO WIRES NAILS OR OTHER MATERIAL MAY BE ATTACHED TO PROTECTED TREES
- 10. TREES, TREE LIMBS, BUSHES AND SHRUBS LOCATED IN THE CITY STREET OR ALLEY IRLES, THEE LIMBS, BUSINES AND SHOUDS LOCATED IN THE CITY STREET OF ALLET RIGHT-OF-WAY OR PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSED CONSTRUCTION ACTIVITIES SHALL BE PROPERLY PRUNED FOLLOWING THE ANSI A-300 STANDARDS FOR PRUNING. ALL TREE PRUNING SHALL BE COMPLETED BY A CITY OF SAN ANTONIO TREE MAINTENANCE LICENSED CONTRACTOR (ARTICLE 21-17), CITY CODE) ONLY AFTER APPROVAL FROM THE CAPITAL PROJECTS MANAGEMENT THROUGH THE INSPECTOR.
- 11. NO EXCESSIVE TREE TRIMMING WILL BE PERMITTED
- 12. ALL DEBRIS GENERATED BY THE PRUNING AND TRIMMING OF THE TREES AND /OR BUSHES SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF PROPERLY (NO SEPARATE PAY ITEM).
- TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS.
 MAINTENANCE MAY INCLUDE, BUT NOT LIMITED TO: WATERING THE ROOT PROTECTION ZONE. WASHING FOLIAGE, FERTILIZATION, PRUNING, ADDITIONAL MULCH APPLICATIONS AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT.
- 14. ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST. (207-8053)
- 15. TREES WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE CITY'S SATISFACTION.
- 16. TREE PLANTING FOR MITIGATION OR ENHANCEMENT: ALL PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATION, FERTILIZING, PRUNING AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT. TREES THAT DIE WITHIN TWELVE (12) MONTHS SHALL BE REPLACED WITH A TREE OF EQUAL SIZE AND SPECIES.

ACCESSIBILITY REQUIREMENTS

- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES TO LOCAL RESIDENCES AND BUSINESSES.
- WHEN THE WORK REQUIRES THE EXCAVATION OF THE STREET AND THE REMOVAL OF THE EXISTING DRIVEWAY APPROACHES AND SIDEWALKS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY ALL-WEATHER ACCESS TO THE BUSINESSES AND RESIDENCES. THE TEMPORARY DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH FLEXIBLE BASE OR GRAVEL MATERIAL AT NO SEPARATE COST TO THE CITY
- PRIOR TO INITIATING THE CONSTRUCTION OF NEW DRIVEWAY APPROACHES, THE CONTRACTOR SHALL GIVE ADVANCE WARNING IN PERSON, OR IN WRITING, OF AT LEAST 48 HOURS TO EACH RESIDENCE THAT WILL BE IMMEDIATELY AFFECTED, SO THAT ALTERNATE PLANS MAY BE MADE
- FOR BUSINESSES WITH MORE THAN ONE DRIVEWAY, AT LEAST ONE DRIVEWAY SHALL REMAIN OPEN WHILE THE OTHER NEW DRIVEWAY APPROACHES ARE CONSTRUCTED. FOR BUSINESSES WITH ONLY ONE DRIVEWAY, THE NEW DRIVEWAY APPROACH SHALL BE CONSTRUCTED IN HALF WIDTHS, UNLESS A TEMPORARY ASPHALT DRIVEWAY IS FIRST INSTALLED AT NO SEPARATE COST

DECEMBER 2009

S0010-0081-01

CITY OF SAN ANTONIO TRANSPORTATION & CAPITAL IMPROVEMENTS

WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322) CITY OF SAN ANTONIO GENERAL NOTES

100 ★ SUBMITTAL PROJECT NO.: 40-00322 DATE: 03/03/2015 DSGN. BY: CHKD, BY: SHEET NO: 8 OF 90

ADDITIONAL NOTES

1. CONTRACTOR SHALL CONTACT METHODIST HOSPITAL AT (210)555-1234 72 HOURS PRIOR TO ANY WORK BEING DONE TO CONCRETE DRIVEWAY @ STA. 484 00 RT.

DELETED NOTES

DELETE NOTE NO.8 - CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY-FOUR (24)
HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES IN ORDER TO SCHEDULE FOR DENSITY
TESTS AS REQUIRED (TELEPHONE NO. 532-2860).

NOTE MODIFICATION

 MODIFY NOTE NO. 4 - CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION ANY DAMAGE DONE TO EXISTING FENCES, CONCRETE ISLANDS, STREET PAVING, CURBS, SHRUBS, BUSHES, EXISTING WOODEN FENCES, ORNAMENTAL STONE PLANTERS, OR DRIVEWAY'S (NO SEPARATE PAY ITEM).

STORM WATER POLLUTION PREVENTION PLAN NOTES

- 1. The Contractor shall prepare a Storm Water Pollution Prevention Plan in accordance with Item 540 and provide a copy of the SW3P plan to the City prior to beginning construction. The cost of all on-site pollution control measures required by the SW3P (eg. silt fencing, construction exits, gravel filters, etc.) shall be included in the lump sum price for Item 553.
- The Contractor shall provide control measures to prevent or minimize the impact to the existing municipal separate storm water systems. The SW3P is to be adjusted and updated as the project progresses to meet compliance with permit and ordinance.
- Contractor shall be responsible for the removal and appropriate disposal of any project control measures not incorporated as a permanent control when final stabilization has been obtained on the project.

PEDESTRIAN NOTES

- Temporary pedestrian crossings may be required. Locations will be decided upon in the field by the Construction Inspector and the Police Department Accident Prevention Bureau. It shall be four feet (4") wide by four inches (4") thick of A.T.B. and comply with Item 206. No direct payment.
- Temporary pedestrian bridges may be required. Locations will be decided upon in the field by the Construction Inspector and Traffic Engineering representative. It shall conform to Item 710-Pedestrian Bridges. No direct payment unless payment under Item 710 is noted on plans.

JONES&CARTER, tac.

Texas Board of Professional Engineers Registration No. F-439
1000 CENTRAL PARKWAY NORTH SUITE 100 — SAN ANTONIO, TEXAS 78232
PHONE: (210) 494—5511 FAX: (210) 494—5519 www.jonescorter.com

CITY OF SAN ANTONIO

WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)

SUPPLEMENTAL GENERAL NOTES

 100
 % SUBMITTAL
 PROJECT NO.
 40-00322
 DATE:
 03/03/2015

 DRWN BY:
 DSGN BY:
 CHKD BY:
 SHT NO.
 9 OF 90

	ITEM NO.	100.1	100.2	101.1	102.1	103.1	103.3	103.4	104.1	108.1	200.1	202.1	203.1	205.4	205.4	208.1	500.1	502.1	503.1	506.1	512.1	512.3	515.1	516.1	520.1
PLAN SHEET NO.	STATION/LOCATION	MOBILIZATION	INSURANCE AND BOND	PREPARING RIGHT OF WAY	OBLITERATING ABANDONED STREET	REMOVE CONCRETE CURB	REMOVE CONCRETE SIDEWALKS AND DRIVEWAYS	REMOVE MISCELLANEOUS CONCRETE	STREET EXCAVATION	LIME TREATED SUBGRADE (6" COMP.)	FLEXIBLE BASE (12" COMPACTED DEPTH)	PRIME COAT	TACK COAT	HOT MIX ASPH. PVMT TYPE D (1.5" COMP.)	HOT MIX ASPH. PVMT TYPE D (2.5" COMP.)	SALVAGING, HAULING & STOCKPILING RECLAIMABLE ASPHALTIC PAVEMENT (1.5")	LAID CURB	CONCRETE SIDEWALKS		CONCRETE RETAINING WALLS - COMBINATION TYPE	ADJUSTING EXISTING MANHOLES	VALVE BOX ADJUSTMENTS	TOPSOIL	BERMUDA SODDING	HYDROMULCHI
		LS	LS	LS	SY	LF	SF	SF	CY	SY	SY	GAL	GAL	SY	SY	SY	LF	SY	SY	CY	EA	EA	CY	SY	SY
BASE BID																									
	WILSON BLVD.																								
24	Pavement Overlay				691				583	1311	1311	138	602	6023	691	5332									
26	0+58.85 TO 3+00.00					188	1414	35									501	84	75	1.5	2		56	302	33
27	3+00.00 TO 5+00.00					191	1116										607	85	20	0			101	343	264
28	5+00.00 TO 7+00.00					200	1835										600	89	116	0			94	285	278
29	7+00.00 TO 9+00.00					191	764										607	85	0	0			108	382	263
30	9+00.00 TO 11+00.00					200	1420										603	89	70	0			85	331	180
31	11+00.00 TO 12+40.82					81	324	9									193	36	0	0.5			28	162	3
61	S.W.P.P.P. PLAN																								
83	Existing Conditions - 1 of 6																					10			
84	Existing Conditions - 2 of 6																					1			
86	Existing Conditions - 4 of 6																					2			
88	Existing Conditions - 6 of 6																					3			
	THESPIAN ISLAND																								
32	Sheet 1				567								16	160		160	397						95	567	
33	Sheet 2				1288	282	1000						47	465		1288	621	178			1		204	1221	
	ATTITUTE AND MONTH OF																								
	STRIPING AND SIGNAGE																								
70	Striping & Signage - 1 of 2								-															-	
71	Striping & Signage - 2 of 2																								
72	Striping & Signage - 1 of 2		-										-						-					-	
73	Striping & Signage - 2 of 2		-	-			-						-		-				-						
	TOTAL	1	1	1	2546	1333	7873	44	583	1311	1311	138	665	6648	691	6780	4129	646	281	2	.3	16	770	3593	1021
	TOTAL	1 1	7	1 7	2046	1555	16/3	44	583	1311	1311	138	005	0048	097	0/80	4129	046	287	Z	3	/6	170	3593	1021

1	ITEM NO.	530.1	531.03	531.06	531.18	531.2	531.34	531.35	531.36	531.51	531.57	531.59	531.69	531.75	535.01	535.02	535.07	535.09	535.12	535.17	540.06	540.10	553.00	801.2
PLAN SHEET NO.	STATION/LOCATION	BARRICADES, SIGNS & TRAFFIC HANDLING	STOP (HIGH	R2-1 SPEED LIMIT (HIGH DENSITY)	H K6-1 DO NOT	R6-2 ONE WAY	S1-1 ADVANCE SCHOOL CROSSING & SCHOOL CROSSING	DIAGONAL		W11-2 PED.	9 INCH STREET NAME, BLOCK NUMBERS	SPECIAL SIGN VIA BUS STOP	R3-17A AHEAD	D11-1 BIKE ROUTE	4" WIDE YELLOW LINE	4" WIDE WHITE LINE	24" WIDE WHITE LINE	LEFT WHITE ARROW	WORD "ONLY"	BICYCLE RIDER SYMBOL	CONSTRUCTION EXIT (INSTALL/ REMOVE)	CURB INLET GRAVEL FILTERS	SWPPP	LEVEL IIA PROTECTIVE FENCE TREE TRUNK PROTECTION
		LS	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA	EA	SY	LF	LS	LF
BASE BID					т		, i				,													
DAGE BID	WILSON BLVD.								_															
24	Pavement Overlay																							
26	0+58.85 TO 3+00.00																							200
27	3+00.00 TO 5+00.00																							
28	5+00.00 TO 7+00.00				1		, the state of the																	
29	7+00.00 TO 9+00.00						'																	
30	9+00.00 TO 11+00.00										1										1			
31	11+00.00 TO 12+40.82																							
61	S.W.P.P.P. PLAN																				60	50		
83	Existing Conditions - 1 of 6																							
84	Existing Conditions - 2 of 6																							
86	Existing Conditions - 4 of 6									ļ												$\overline{}$,	
88	Existing Conditions - 6 of 6									ļ'												$\overline{}$		
1 ├──	· · · · · · · · · · · · · · · · · · ·								\perp											\leftarrow		-	,	
1 ——	THESPIAN ISLAND								\vdash													-		
32	Sheet 1							←	-											⊢—		-		
33	Sheet 2							\leftarrow	-									_		-				
1⊢—	STRIPING AND SIGNAGE		-						+											\leftarrow	-	\leftarrow		
70	Striping & Signage - 1 of 2		1		+	4	1	1	1	3	2	-1	- 1	1		940	565	2	-1	6	-	-		
71	Striping & Signage - 1 of 2		1	1	+	1	2	2	+	2	2	1				1154	391	2	1	8		\vdash		-
72	Striping & Signage - 2 of 2 Striping & Signage - 1 of 2		1		+ 1					_						84	10	-		1	<u> </u>			+
73	Striping & Signage - 2 of 2									1					488	445	42			3				
	, 5 5 Jags 2 1 1 2				1		 																	
1 	TOTAL		3														1008					50		200



JONES & CARTER, 180.

Team Board of Physicianal Engineer Agriculture No. 247

1000 CENTRAL PARKWAY NORTH SUITE 100 – SAN ANTONO, 1EXAS 78232

PHONE: (210) 494—5511 FAX: (210) 494–5519 www.jonescorter.com

CITY OF SAN ANTONIO TRANSPORTATION & CAPITAL IMPROVEMENTS

WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)

SUMMARY OF QUANTITIES

SEQUENCE OF WORK NARRATIVE

General

Cooperate in the use of the right-ofway with the City of San Antonio and various public utilities and there contractors, as may be required to allow adjustments to be made by others.

Traffic flow must be planned for the entire project during construction.

Provide access to all adjacent property throughout all phases of construction. Adequacy of access will be at discretion of the Engineer or the City's inspector.

Restore to original or better condition all damage done to existing fences and gates.

Regulate all construction traffic to minimize inconvenience to the traveling public, Provide warning signs and/or flag men if necessary.

Schedule implementation of the SWPPP measures on a phase-by-phase basis covering all soil disturbing activities. Whenever possible preserve the existing vegetation and minimize the amount of disturbed ground throughout the entire project.

■. Right-of-Way Easement Acquisition, Permits and Approvals

The City of San Antonio Transportation & Capital Improvements (TCI) shall secure all right-of-way and easements, including temporary construction easements.

(TCI) shall provide certain permits related to construction of the projects, which are not the responsibility of the Contractor. These may include permits from Corp of Engineers or the Texas Department of Transportation.

The Contractor shall provide all plans requiring review and/or approval of the City prior to construction. These may include but are not limited to a traffic control plan (if required) and a storm water pollution prevention plan (SWPPP) including payment of all fees for such permits.

V. Construction Activities

The Contractor will construct the project in multiple phases in accordance with the phasing and staging notes included in the plans

Each phase of the project will generally include reconstruction of streets, sidewalks and curbs.

Perform all work in Phases 1 through 3 in accordance with the traffic control plan. The new roadway sections will be constructed in full lane widths. Provide positive guidance for traffic through the project area, including traffic entering the work area from intersecting streets and driveways. Notices of detour shall be placed at least 2 weeks prior to road closures. When any work process is not completed in one day, provide a temporary ramp between the new surface and the existing roadway surface at a slope not to exceed 8:1, to allow safe passage of traffic during non-work periods.

Phase 1 (Wilson Blvd. (south bound) from Donaldson Ave. to Club Dr.):

Construction is to commence from the south end of Wilson Blvd. and move north as work progresses.

Install temporary street signage.

Place all SWPPP measures in accordance with the storm water pollution prevention plan.

Provide the tree protection measure outlined in the tree protection plan.

Setup barricades, detour signage and steel street plates as needed in accordance with the traffic control plan and as construction progresses. Overnight street closures should be avoided of possible. Contractor must ensure sufficient access through the construction phase for emergency personnel at all times. Contractor must notify VIA operations to allow for implementation of any bus route detour.

Remove and reconstruct (if required) any existing fencing that conflicts with proposed improvements. Provide temporary fencing as shown on plans until the street construction is completed. After street construction, the Contractor must replace any fencing damaged during construction.

Construct streets including sidewalks, retaining walls, driveway. The Contractor must ensure that all valve boxes, manhole rings and covers, and aprons in front of curb inlets are adjusted properly to provide a smooth finish when the final course of asphalt is laid.

The Contractor may commence construction in the following phase upon completion of street base and approval of the base densities.

Complete adjustments and/or reconstruction of fences, driveway gates and pedestrian gates.

Revegitate all disturbed areas, remove temporary SWPPP measures, temporary signage.

Thespian Island construction may commence at anytime during Phase 1, 2 or 3.

Phase 2 (Wilson Blvd. (north bound) from Donaldson Ave. to Club Dr.)

All construction is to commence from south end of Wilson Blvd. and move north as work progresses.

Install temporary street signage.

Place all SWPPP measures in accordance with the storm water pollution prevention plan.

Provide the tree protection measures outlined in the tree protection plan.

Setup barricades, detour signage and steel street plates as needed in accordance withe the traffic control plan and as construction progresses. Overnight street closures should be avoided if possible. Contractor must ensure sufficient access through the construction phase for emergency personnel at all times. Contractor must notify VIA operations to allow for implementation of any bus route detour.

Remove and reconstruct (if required) any existing fencing that conflicts with the proposed improvements. Provide temporary fencing as shown on plans until the street construction is completed. After street construction, the Contractor must replace any fencing damaged during construction.

Construct streets including sidewalks, retaining walls, driveways. The Contractor must ensure that all valve boxes, manhole rings and covers, and aprons in front of curb inlets are adjusted properly to provide a smooth finish when the final course of asphalt is laid.

The Contractor may commence construction is the following phase upon completion milling activities.

S0010-0081-01



 1000 CENTRAL, PARKWAY NORTH SUITE 100 - SAN ANTONIO, TEXAS 78232

 PHONE: (210) 494-5511
 FAX: (210) 494-5519
 www.jonescarter.com

CITY OF SAN ANTONIO

WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)

SEQUENCE OF WORK 1 OF 2

100 % SUBMITTAL PROJECT NO. 40-00322 DATE: 03/03/2015 DRWN BY: KS/JS DSGN BY: JSB CHKD BY: JSB SHT NO. 11 0F 90

CHARLES GRADY KOEHL

Complete adjustments and/or reconstruction of fences, driveway gates and pedestrian gates.

Revegitate all disturbed areas, remove temporary SWPPP measures, temporary signage.

Phase 3 (Wilson Blvd, (median & turn lanes) from Donaldson Ave. to Club Dr.)

All construction is to commence from the south end of Wilson Blvd, and move north as work progresses.

Install temporary street signage.

Place all SWPPP measures in accordance with the storm water pollution prevention plan.

Provide the tree protection measures outlined in the tree protection plan.

Setup barricades, detour signage and steel plates as needed in accordance with the traffic control plan and as construction progresses. Overnight street closures should be avoided if possible. Contractor must ensure sufficient access through the construction phase for emergency personnel at all times. Contractor must notify VIA operation to allow for implementation of any bus route detour.

Remove and reconstruct (if required) any existing fencing that conflicts with the proposed improvements. Provide temporary fencing as shown on plans until the street construction is completed. After street construction, the Contractor must replace any fencing damaged during construction.

Construct streets including concrete median. The Contractor must ensure that all valve boxes, manhole rings and covers, and aprons in front of curb inlets are adjusted properly to provide a smooth finish when the final curse of asphalt is laid.

Complete adjustments and/or reconstruction of fences, driveway gates and pedestrian gates.

Revegitate all disturbed areas, remove temporary SWPPP measures, temporary signage.

V. Roadside Sign Relocation

When all construction has been performed in each phase. Install the new signs at the locations shown on the Pavement Marking and Signage Plan. Provide new foundations, post and hardware for all signs. All existing post, foundations, and hardware will be disposed of in an approved manner at no separate pay. Any sign to be removed will remain the property of the City. Stockpile the remove signs in an approved location. Replace any signs damaged by the construction activities.

VI. Final Cleanup, Permit Termination and Inspections

Remove all surplus materials from the project. Sod all areas requiring vegetation in accordance with the plans. Complete final cleanup and inspection punch list items.

Attend inspection of sidewalks and crossings for ADA compliance and replace or resolve all problem areas.

VII. Payment

Unless otherwise indicated on the plans or within specifications, all work and materials required to complete the phasing and sequence of work will be considered subsidiary to the various bid items within the contract.

CHARLES GRADY KOEHL
8.3945

S0010-0081-01

JONES & CARTER, INC.

1000 CENTRAL PARKWY NORTH SUITE 100 — SAN ANTONIO, TEXAS 78232
PHONE: (210) 494—5511 FAX: (210) 494—5519 www.jonescarter.com

CITY OF SAN ANTONIO TRANSPORTATION & CAPITAL IMPROVEMENTS


WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)


SEQUENCE OF WORK 2 OF 2


 100 % SUBMITTAL
 PROJECT NO.
 40-00322
 DATE: 03/03/2015


 DRWN BY:
 KS/JS
 DSGN BY:
 JSB
 CHKD BY:
 JSB
 SHT NO.
 12 0F 90


©2015 Jones & Carter, Inc.






























THESPIAN ISLAND STREET CROSS SECTION "A-A"






TRANSPORTATION & CAPITAL IMPROVEMENTS

WILSON BLVD. (CLUB-DONALDSON) & THESPIAN ISLAND (40-00322)

STREET CROSS SECTIONS DETAILS FOR THESPIAN ISLAND

100 % SUBMITTAL PROJECT NO. 40-00322 DATE: 03/03/2015





DATE: 03/03/2015 SHT NO, 35 0F 90





TEXAS HISTORICAL COMMISSION

real places telling real stories

April 13, 2015

Adriana Ziga Office of Historic Preservation City of San Antonio 1901 S. Alamo San Antonio, TX 78204

Re: Project review under the Antiquities Code of Texas

Proposed improvements at Thespian Island and along Wilson Blvd, Thomas Jefferson High School, San Antonio,

Bexar County (NR, RTHL)

Dear Ms. Ziga:

Thank you for your correspondence regarding the above referenced project which we received on April 10, 2015. This letter presents the comments of the Executive Director of the Texas Historical Commission, the state agency responsible for administering the Antiquities Code of Texas.

The review staff, led by Sara Ludueña, has completed its review of the project documentation provided. We find that the proposed improvements around the Thespian Island and along Wilson Boulevard at Thomas Jefferson High School, which are intended to increase pedestrian and vehicular safety in these areas, will have **no adverse effect** on the historic Jefferson High School.

We look forward to further consultation with your office and hope to maintain a partnership that will foster effective historic preservation. Thank you for your cooperation in this federal review process, and for your efforts to preserve the irreplaceable heritage of Texas. If you have any questions concerning our review or if we can be of further assistance, please contact Sara Ludueña at 512/463-8952.

Sincerely,

Sara Ludueña, Project Reviewer

for: Mark Wolfe, State Historic Preservation Officer

cc: Virginia S. Nicholas, Chair, Bexar County Historical Commission

MW/sl

