SAN ANTONIO WATER SYSTEM



SEWER JOB NO: 18-4540

100% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583
7/17/2019
THIS DOCUMENT IS NOT INTENDED


THIS DOCUMENT IS NOT INTENDED FOR BIDDING,PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL

SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE

SUBMITTAL PREPARED BY:





JULY 2019

	SHEET INDEX
1	TITLE SHEET
2	GENERAL NOTES
3	PROJECT SPECIFIC NOTES AND QUANTITIES
4	PROJECT LAYOUT
5	CIPP - PROJECT LOCATION 1 - BEGIN TO STA 7+00
6	CIPP - PROJECT LOCATION 1 - STA 7+00 TO END
7	CIPP - PROJECT LOCATION 2 - BEGIN TO STA 4+00
8	CIPP - PROJECT LOCATION 2 - STA 4+00 TO 8+00
9	CIPP - PROJECT LOCATION 2 - STA 8+00 TO 12+00
10	CIPP - PROJECT LOCATION 2 - STA 12+00 TO 16+00
11	CIPP - PROJECT LOCATION 2 - STA 16+00 TO 20+00
12	CIPP - PROJECT LOCATION 2 - STA 20+00 TO 24+00
13	CIPP - PROJECT LOCATION 2 - STA 24+00 TO 28+00
14	CIPP - PROJECT LOCATION 2 - STA 28+00 TO 32+00
15	CIPP - PROJECT LOCATION 2 - STA 32+00 TO END
16	OVERALL BYPASS PLAN
17	PROPOSED BYPASS PLAN - 1 OF 5
18	PROPOSED BYPASS PLAN - 2 OF 5
19	PROPOSED BYPASS PLAN - 3 OF 5
20	PROPOSED BYPASS PLAN - 4 OF 5
21	PROPOSED BYPASS PLAN - 5 OF 5
22	TRAFFIC CONTROL PLAN
23	OVERALL ACCESS ROUTE
24	GOLF COURSE ACCESS AND RESTORATION - 1 OF 8
25	GOLF COURSE ACCESS AND RESTORATION - 2 OF 8
26	GOLF COURSE ACCESS AND RESTORATION - 3 OF 8
27	GOLF COURSE ACCESS AND RESTORATION - 4 OF 8
28	GOLF COURSE ACCESS AND RESTORATION - 5 OF 8
29	GOLF COURSE ACCESS AND RESTORATION - 6 OF 8
30	GOLF COURSE ACCESS AND RESTORATION - 7 OF 8
31	CONTRACTOR ACCESS - APARTMENT COMPLEX - 8 OF
32	TREE CANOPY ASSESSMENT - 1 OF 8
33	TREE CANOPY ASSESSMENT - 2 OF 8
34	TREE CANOPY ASSESSMENT - 3 OF 8
35	TREE CANOPY ASSESSMENT - 4 OF 8
36	TREE CANOPY ASSESSMENT - 5 OF 8
37	TREE CANOPY ASSESSMENT - 6 OF 8
38	TREE CANOPY ASSESSMENT - 7 OF 8
39	TREE CANOPY ASSESSMENT - 8 OF 8
40	AS-BUILT REFERENCE
41	DETAILS
42	EROSION CONTROL - EPIC SHEET
43	EROSION CONTROL - DETAIL SHEET (1 OF 2)
44	EROSION CONTROL - DETAIL SHEET (2 OF 2)
45	TREE PROTECTION DETAILS

- GENERAL SECTION:
 1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE
 - APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND COMPLY WITH THE PLANS,
 SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:

 A. CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) "DESIGN CRITERIA FOR
 DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1
 - CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290. CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE.
 - CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION."
 CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR CONSTRUCTION."
 - CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).
- THE CONTRACTOR SHALL OBTAIN SAWS STANDARD DETAILS FROM SAWS WEBSITE, HTTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHERWISE NOTED WITHIN DESIGN
- THE CONTRACTOR IS TO NOTIFY AND MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 210-233-3500, AND PROVIDE NOTIFICATION PROCEDURES THE CONTRACTOR WILL USE TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 72 HOURS PRIOR TO EXCAVATION.
- LOCATIONS AND DEPTHS OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS.
- THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:

SAN ANTONIO WATER SYSTEM:

SAWS UTILITY LOCATES: HTTP://WWW.SAWS.ORG/SERVICE/LOCATES COSA DRAINAGE 210-207-8048

COSA TRAFFIC SIGNAL OPERATIONS 210-207-7720

TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811

- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION AS A RESULT OF DAMAGES DONE BY THE PROJECT'S CONSTRUCTION.
- ALL WORK IN TEXAS HIGHWAY DEPARTMENT AND BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT.
- THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- 10. ANY WORK COMPLETED WITHOUT PRIOR WRITTEN AUTHORIZATION WHICH IS NOT INCLUDED IN THESE PLANS AND SPECIFICATIONS WILL NOT BE COMPENSATED BY THE SAN ANTONIO WATER
- 11. HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.

WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION CONSTRUCTION DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG

ANY AND ALL SAWS UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION.

- 12. PRE CON SITE VIDEO: BEFORE THE START OF ANY CONSTRUCTION. THE SITE MUST BE VIDEO RECORDED BY THE CONTRACTOR WITH ONE COPY SUBMITTED TO SAWS INSPECTIONS. A PRE-SITE VIDEO WILL PROVIDE ACCURATE DOCUMENTATION OF THE EXISTING CONDITIONS (NSPI).
- 13. POWER POLE BRACING: CONTRACTORS SHOULD BE ADVISED THAT THERE ARE EXISTING OVERHEAD POWER POLE BRACING: CONINACIONS SHOULD BE ADVISED THAT THERE ARE EXISTING OVERHEAD UTILITY POLES ALONG THE PROJECT CORRIDOR. CONTRACTORS SHOULD FURTHER BE ADVISED THAT IF THE DISTANCE FROM THE OUTSIDE FACE OF A UTILITY TRENCH TO THE FACE OF A UTILITY POLE IS LESS THAN 5 FEET, SAID UTILITY POLE IS SUBJECT TO BRACING, BASED ON A DETERMINATION MADE BY UTILITY POLE OWNER. COSTS INCURRED BY CONTRACTOR FOR BRACING OF THESE UTILITY POLES IS SUBSIDIARY TO THAT RESPECTIVE UTILITY COMPANY'S WORK. IT IS ADVISABLE FOR THE CONTRACTOR TO REVIEW THE CONSTRUCTION DOCUMENTS, AND VISIT THE CONSTRUCTION SITE TO DETERMINE POTENTIAL IMPACTS.
- CONSTRUCTION SEQUENCING: IT IS THE CONTRACTOR SOLE RESPONSIBILITY TO SCHEDULE SEQUENCING FOR REMOVAL AND INSTALLATION OF EXISTING AND PROPOSED SAWS UTILITIES IN CONJUNCTION WITH GENERAL PROJECT CONSTRUCTION. SEQUENCE OF CONSTRUCTION ACTIVITIES SHALL BE CONSIDERED IN ORDER TO MINIMIZE THE EXTENT AND DURATION OF DISTURBANCES.

- SEWER SECTION:
 15. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:
 - IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT 210-704-SAWS (210-704-7297). PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW.
 - ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO.
 - CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS.
 - CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.
 - CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS. MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE

CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM

NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE TCEQ AND SAWS. 16. THE CONTRACTOR SHALL PROVIDE BYPASS PUMPING OF SEWAGE AROUND FACH SEGMENT OF PIPE TO

- BE REPLACED, IN ACCORDANCE WITH SAWS SPECIFICATION ITEM NO. 864-S1, "BYPASS PUMPING SMALL DIAMETER SANITARY SEWERS" AND ITEM NO. SP864-S2, "BYPASS PUMPING". PAYMENT FOR SUCH WORK WILL BE MADE UNDER THE BID ITEM "BYPASS PUMPING" (PER EACH) AS PER SAWS SPECIAL SPECIFICATION.
- 17. PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 210-233-3500 AND/OR SAWS PRODUCTION GROUPS AT LEAST ONE WEEK OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS: THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
- 18. ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS (NSPI).
- SMART MANHOLE COVERS: THE CONTRACTOR SHALL NOTIFY JUAN C. RAMIREZ AT 210-233-3558 AND SAWS EOC AT 210-704-SAWS (210-233-7297) A MINIMUM OF 72 HOURS, NOT COUNTING WEEKENDS OR SAWS HOLIDAYS, BEFORE WORKING ON THE PIPE OR MANHOLE, IN ORDER TO HAVE SAWS REMOVE THE SMART COVER. ANY DAMAGE DONE TO THE SMART COVER WILL BE CHARGED TO THE CONTRACTOR THROUGH A CHANGE ORDER.

- NOTES:
 1. CONTRACTOR TO MAINTAIN SEWER LATERALS AT ALL TIMES DURING CONSTRUCTION. CONTRACTOR SHALL ALSO MAINTAIN ACCESS TO ALL EXISTING AND PROPOSED WATER VALVES AT ALL TIMES (NSPI).
- 2. NSPI NOT A SEPARATE PAY ITEM.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING OPERATION OF ALL EXISTING UTILITIES AFFECTED BY PROPOSED CONSTRUCTION.
- TREE REMOVAL IS NOT PERMITTED ON THIS PROJECT UNLESS NOTED OTHERWISE BY CALLOUTS IN THE PLANS. CONTRACTOR SHALL TAKE EXTREME CARE WHEN WORKING AROUND TREES TO PREVENT DAMAGE. PRIOR TO THE START OF WORK, CALL 207-1111 TO SCHEDULE A PRE-CONSTRUCTION FENCING INSPECTION. TREE PROTECTION AND PRUNING OF TREES REQUIRED TO CLEAR RIGHT OF WAY OR EASEMENTS AND ALL ONSITE TREE REMOVAL WILL BE DONE AT CONTRACTOR'S EXPENSE (NSPI).

- CALL THE TEXAS STATE WIDE ONE CALL LOCATOR NUMBER 1-800-545-6005, 48 HOURS BEFORE BEGINNING ANY EXCAVATION.
- DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.181, CPS ENERGY MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN PROJECT AREA.
- 3. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING CPS ENERGY OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES IF ADJACENT TO WORK AREAS.
- 4. CONTRACTOR TO FIELD VERIFY THE DEPTH OF GAS MAINS BEFORE BEGINNING OF CONSTRUCTION.

- THE EXISTENCE AND LOCATION OF UNDERGROUND CABLE INDICATED ON THE PLANS ARE TAKEN FROM THE BEST RECORDS AVAILABLE AND ARE NOT GUARANTEED TO BE ACCURATE.
- 2. THE CONTRACTOR SHOULD CALL FOR LOCATES THROUGH THE "ONE CALL" UTILITY LOCATE SERVICE (1-800-545-6005) 48 HOURS PRIOR TO CONSTRUCTION/EXCAVATION WORK. CONTRACTORS HAVE THE RESPONSIBILITY TO PROTECT AND SUPPORT TELEPHONE COMPANY PLANT DURING CONSTRUCTION.

NOTE FOR THE CITY OF SAN ANTONIO FLATWORK:

ALL LIMITS FOR CURB, SIDEWALK, AND TREE PREP BEYOND WHAT IS CONSIDERED INCIDENTAL TO NORMAL UTILITY CONSTRUCTION WILL BE ADDRESSED BY THE SAWS INSPECTOR. SAWS INSPECTOR WILL ALSO DETERMINE IF ADDITIONAL COMPENSATION IS WARRANTED IF LIMITS EXCEED INCIDENTALS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH, AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS, SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OF SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

- THE CONTRACTOR SHALL NOT HAVE EXCLUSIVE USE OF THE RIGHT OF WAY BUT SHALL COOPERATE IN THE USE OF THE RIGHT OF WAY WITH THE CITY OF SAN ANTONIO, TEXAS DEPARTMENT OF TRANSPORTATION, AS WELL AS VARIOUS PUBLIC UTILITY COMPANIES AS MAY BE REQUIRED. IN THE EVENT OF UNFORESEEN UTILITY ADJUSTMENTS, THE CONTRACTOR SHALL EXECUTE WORK IN SUCH A MANNER AND SEQUENCE AS TO ALLOW THE ADJUSTMENTS TO BE MADE WITH MINIMAL DISRUPTION TO TRAFFIC.
- TRAFFIC MUST BE HANDLED APPROPRIATELY THROUGH THE PROJECT DURING CONSTRUCTION AND IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE FOR THE SAFETY AND COMFORT OF THE TRAVELING PUBLIC AT ALL TIMES.
- THE CONTRACTOR'S ATTENTION IS CALLED TO THE NECESSITY OF ERECTING AND MAINTAINING BARRICADES, WARNING SIGNS, AND DIRECTIONAL SIGNS AT ALL APPROACH STREET INTERSECTIONS IN ORDER TO PROPERLY DIRECT TRAFFIC WITHIN THE LIMITS OF THIS PROJECT. ALL SUCH BARRICADES, WARNING SIGNS, AND DIRECTIONAL SIGNS SHALL COMPLY WITH THE LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD).
- CONTRACTOR SHALL PROVIDE FOR THE SAFE MOVEMENT OF ALL PEDESTRIAN TRAFFIC, GOLF COURSE TRAFFIC, AND BICYCLE TRAFFIC IN AND AROUND THE CONSTRUCTION AREA DURING THE CONSTRUCTION PHASING. ALL SUCH BARRICADES, WARNING SIGNS, AND DIRECTIONAL SIGNS SHALL COMPLY WITH THE LATEST EDITION OF THE TMUTCD.

100% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583

K·FRIESE + ASSOCIATES PUBLIC PROJECT ENGINEE
10001 Reunion Place
Suite 404
San Antonio, Texas 78216
P 210.491.291 F 512.338.1784
IBPE Firm Number 6535
www.kfriese.com

DR. MW CK.

7/17/2019 THIS DOCUMENT IS NOT INTENDED FOR BIDDING.PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL

No.	Rev	ision	Drawn	Approved	Date
REVISIONS					
	35	SILVERH 24-INC	IORN C	OLF COAB PAC	OURSE KAGE

750 l	24-INCH REHAB PACKA
	GENERAL NOTES

DEVELOPER:		
CONT.	BUDGET PROJ.	
SUBMITTED		
APPROVED		
MAP No.		SHEE
SECT. No.		2

- SEWER REHABILITATION NOTES:


 THESE PLANS WERE PREPARED WITH LIMITED ON THE GROUND SURVEY. AERIAL IMAGERY MAY NOT REFLECT ALL RECENT IMPROVEMENTS. CONTRACTOR SHALL FIELD VERIFY SITE CONDITIONS AND ELEVATIONS PRIOR TO CONSTRUCTION.
- PROFILES SHOWN IN PLANS FOR CIPP SEGMENTS ARE BASED ON BEST INFORMATION AVAILABLE. INVERTS ARE BASED ON SAWS GIS DATA AND LIMITED FIELD SURVEY. INFORMATION IS PROVIDED TO ASSIST CONTRACTOR WITH PLANNING INSTALLATION. SLIGHT DISCREPANCIES WITH MANHOLE ELEVATIONS MAY BE ENCOUNTERED; CONTRACTOR SHALL FIELD VERIFY.
- ALL POINT REPAIRS MUST BE CONFIRMED AND APPROVED BY SAWS AND DESIGN ENGINEER VIA PRE-TELEVISING PRIOR TO CONSTRUCTION.
- CONTROL NOISE LEVEL DURING NIGHT HOURS IN ACCORDANCE WITH CITY OF SAN ANTONIO NOISE ORDINANCES, EXCEPT AS MODIFIED BELOW. CONSTRUCTION
 ACTIVITIES AND EQUIPMENT FOR ACTIVITIES BETWEEN THE HOURS OF 6 P.M. AND 7 A.M. SHALL BE EQUIPPED WITH ACOUSTICAL ENCLOSURES TO LIMIT NOISE LEVEL TO 56 DECIBELS WHEN MEASURED AT ADJACENT RESIDENTIAL PROPERTY LINE OR 63 DECIBELS WHEN MEASURED AT ADJACENT BUSINESS ZONED PROPERTY LINE. DAYTIME NOISE LEVELS (7 A.M. TO 6 P.M.) SHALL NOT EXCEED 80 DECIBELS WHEN MEASURED AT NEAREST PROPERTY LINE.
- CONTRACTOR SHALL BE AWARE THAT PROPOSED CIPP WILL LINE THROUGH MINOR JOINT OFFSETS, MINOR SAGS, AND OTHER MINOR PIPE DEFECTS. MORE SIGNIFICANT DEFECTS THAT NEED TO BE LINED THROUGH ARE SPECIFICALLY CALLED OUT IN THE PLANS OR ARE PROPOSED TO BE POINT REPAIRED.
- REHABILITATED MANHOLES SHALL RECEIVE A NEW RING AND COVER TO MATCH THE EXISTING DIAMETER PER ITEM NO. 851 AS INDICATED IN THE DRAWINGS. RECONSTRUCTED MANHOLES SHALL RECEIVE A NEW 32" COVER, REGARDLESS OF EXISTING COVER SIZE. NOTE THAT SOME MANHOLE COVERS WITHIN THE PROJECT LIMITS HAVE BEEN UPGRADED TO THE CURRENT STANDARDS BY SAWS. THESE MANHOLES WILL NOT REQUIRE A NEW RING AND COVER UNDER ITEM 851. CONTRACTOR TO REPORT ANY DISCREPANCES IN MANHOLE LID REPLACEMENTS TO ENGINEER AND SAWS INSPECTOR.
- 7. NEW MANHOLES INSTALLED FOR BYPASS SUCTION POINTS SHALL BE CONSTRUCTED PER SAWS STD DWG DD-852-01. CONTRACTOR SHALL SUBMIT DETAILS FOR DOGHOUSE MANHOLE INSTALLATION AS PART OF SUBMITTAL PROCESS.
- CONTRACTOR IS ADVISED THAT HANGING GASKETS ARE PRESENT THROUGHOUT PIPELINE SEGMENT. REMOVAL OF HANGING GASKETS FOR CIPP INSTALLATIONS SHALL BE SUBSIDIARY TO ITEM 868 SANITARY SEWER SYSTEM CLEANING.
- ADDITIONAL POINT REPAIRS AND OBSTRUCTION REMOVALS HAVE BEEN INCLUDED IN THE TOTAL ESTIMATED QUANTITIES TABLE DUE TO THE UNKNOWN CONDITION OF THE

- TCI STORM WATER ENGINEERING NOTES:

 1. WORK WITHIN THE 100-YEAR FLOODPLAIN OR CITY OF SAN ANTONIO DRAINAGE CHANNELS IS SUBJECT TO THE TERMS OF THE FLOODPLAIN DEVELOPMENT PERMIT ISSUED BY THE CITY. A COPY OF THIS PERMIT IS INCLUDED IN THE BID DOCUMENTS FOR THE CONTRACTOR'S USE.
- CONTRACTOR IS RESPONSIBLE FOR PROTECTING EXISTING DRAINAGE FACILITIES FROM DAMAGE. ANY DAMAGE TO EXISTING DRAINAGE SYSTEMS, WHETHER OR NOT SHOWN ON THE PLANS, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR AT HIS EXPENSE. THE CONTRACTOR SHALL NOTIFY STORM WATER ENGINEERING AT 210-207-8052 AS SOON AS CONFLICTS WITH UTILITIES ARE ENCOUNTERED OR ANY DRAINAGE SYSTEM IS DAMAGED DURING CONSTRUCTION.
- 3. CONSTRUCTION SPOILS WILL NOT BE ALLOWED TO BE DEPOSITED ANYWHERE WITHIN A DRAINAGE EASEMENT, RIGHT-OF-WAY, OR FLOODPLAIN WITHIN THE LIMITS OF THE PROJECT AND SHALL BE DISPOSED OFFSITE IN COMPLIANCE WITH CURRENT APPLICABLE REGULATIONS.

- GOLF COURSE NOTES:

 1. CONTRACTOR IS ADVISED THAT SILVERHORN GOLF COURSE WILL MAINTAIN NORMAL OPERATIONS THROUGHOUT THE CONSTRUCTION PROJECT. CONSTRUCTION WORK SHALL BE SCHEDULED MONDAY THOUGH FRIDAY; REFER TO THE SPECIAL CONDITIONS FOR CONSTRUCTION TIMELINE LIMITATIONS AND CONTACT INFORMATION.
- PRIMARY CONSTRUCTION ACCESS ROUTE SHOWN IN THE PLANS SHALL SERVE AS THE CONTRACTOR'S PRIMARY INGRESS AND EGRESS ROUTE. THE SECONDARY CONSTRUCTION ACCESS ROUTE SHOWN IS STRICTLY FOR ACCESS TO MANHOLES AND POINT REPAIRS (IF NEEDED). CONTRACTOR SHALL LIMIT USE OF SECONDARY CONSTRUCTION ACCESS TO MINIMIZE IMPACTS TO THE GOLF COURSE. REFER TO SHEET 23-31 FOR PRIMARY AND SECONDARY ACCESS ROUTES.
- CONTRACTOR TO MINIMIZE INGRESS/EGRESS WHEREVER POSSIBLE TO MINIMIZE THE AMOUNT OF REMOVAL OF EXISTING VEGETATION AND DISTURBED AREA FOR THE PROJECT. CONSTRUCTION ACCESS ROUTES SHOWN ON SHEETS 23-30 ARE INTENDED TO MINIMIZE CONFLICTS WITH GOLF COURSE OPERATIONS AND CUSTOMERS AND REDUCE AMOUNT OF TREE/VEGETATION CLEARING, CONTRACTOR MAY MODIFY LOCATION OF CLEARING SLIGHTLY WITHIN THE ACCESS AREA SHOWN BASED ON FIELD CONDITIONS AND HIS OPERATIONS, BUT IN NO CASE SHALL TREE CLEARING WIDTH EXCEED LIMITS SHOWN IN THE DETAIL ON SHEET 23 IN ORDER TO MAINTAIN COMPLIANCE WITH TREE PERMIT FROM CITY OF SAN ANTONIO.
- CONTRACTOR SHALL MINIMIZE CLEARING WITHIN THE CONSTRUCTION ACCESS AREA TO MAINTAIN EXISTING TREE CANOPY. IN NO INSTANCE SHALL HERITAGE TREES (24" AND LARGER) BE REMOVED. HERITAGE TREES ARE SHOWN IN THE PLANS AND TAGGED IN THE FIELD. HERITAGE TREES AND TREES TO REMAIN WITHIN THE ACCESS AREA SHALL BE PROTECTED PER CITY OF SAN ANTONIO TREE PROTECTION DETAILS (NSPI).TREES/VEGETATION REMOVED FOR CONSTRUCTION ACCESS MAY BE MULCHED WITHIN THE ACCESS AREA AND SHALL BE STOCKPILED AT LOCATIONS DESIGNATED BY SILVERHORN GOLF COURSE, STOCKPILED MULCH MAY NOT BE PLACED IN THE 100-YEAR FLOODPLAIN. SEE TREE CLEARING LIMITS AND ACCESS AREA ON SHEETS 32-39.
- CONTRACTOR SHALL AVOID DAMAGE OF ANY KIND TO THE GOLF CART PATHS, GREENS, OR FAIRWAYS UNLESS IDENTIFIED ON THE PLANS FOR REPLACEMENT. CONTRACTOR SHALL PROVIDE TEMPORARY RESTORATION USING 4" COLD MIX ASPHALT AS NEEDED UNTIL FINAL RESTORATION IS COMPLETE, ANY DAMAGE DONE OUTSIDE THE ACCESS EASEMENT SHOWN SHALL BE REPAIRED TO ITS ORIGINAL OR BETTER CONDITION AT THE CONTRACTOR'S EXPENSE.
- 6. THE CONTRACTOR SHALL MAINTAIN ACCESS ON ALL CART PATHS. BYPASS PIPING SHALL BE BURIED AT LOCATIONS SHOWN IN THE PLANS.
- RESTORATION OF CONSTRUCTION AREAS SHALL BE IN ACCORDANCE WITH THE GOLF COURSE ACCESS AND RESTORATION SHEETS 24-31. CONTRACTOR SHALL USE PROTECTIVE MATS WHERE SHOWN IN THE ACCESS AND RESTORATION SHEETS TO MINIMIZE IMPACTS TO GOLF COURSE FAIRWAYS AND GREENS. FAIRWAYS AND GREENS SHALL BE RESTORED UNDER PAY ITEM 1020 "GOLF COURSE RESTORATION ALLOWANCE".



CONCRETE SIDEWALK SECTION ITEM 502 SCALE : NTS

	TOTAL ESTIMATED QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	QUANTITY		
100	MOBILIZATION	LS	1		
SP100.1	INTERMEDIATE DEMOBILIZATION/REMOBILIZATION	EA	1		
SP100.2	INTERMEDIATE DEMOBILIZATION BYPASS EQUIPMENT RENTAL	DAY	10		
SP100.3	INTERMEDIATE DEMOBILIZATION BYPASS PUMPING FUEL	DAY	10		
SP100.4	INTERMEDIATE DEMOBILIZATION BYPASS PUMPING WATCH	DAY	10		
101	PREPARING RIGHT-OF-WAY	LS	1		
103.3	REMOVE SIDEWALKS AND DRIVEWAYS (COSA SPEC)	SF	5051		
SP164.1	CELLULOSE FIBER MULCH SEEDING (PERM) (TXDOT SPEC)	SY	24992		
SP164.2	DRILL SEEDING (PERM) (TXDOT SPEC)	SY	1003		
205.2	HOT MIX ASPHALTIC PAVEMENT – TYPE B (4" COMPACTED DEPTH) (COSA SPEC)	SY	46		
502	CONCRETE SIDEWALK (COSA SPEC)	SY	562		
515	TOPSOIL (4" THICK)	SY	4341		
516.1	BERMUDA SODDING (COSA SPEC)	SY	4341		
SP530	BARRICADES, SIGNS, AND TRAFFIC HANDLING (COSA SPEC)	LS	1		
CDE 40	TEMPORARY EROSION, SEDIMENT, AND WATER POLLUTION	1.6			
SP540	PREVENTION AND CONTROL (COSA SPEC)	LS	1		
550	TRENCH EXCAVATION SAFETY PROTECTION	LF	140		
SP552.1	REPLACE SPRINKLER HEAD	EA	5		
SP552.2	REPAIR IRRIGATION PIPING (UP TO 2" DIAMETER)	EA	5		
SP552.3	REPAIR IRRIGATION PIPING (3" TO 4" DIAMETER)	EA	5		
SP552.4	REPLACE IRRIGATION CONTROL VALVE (UP TO 2" DIAMETER)	EA	5		
SP552.5	REPLACE IRRIGATION CONTROL VALVE (3" TO 4" DIAMETER)	EA	5		
851	ADJUST EXISTING MANHOLES	EA	10		
852	4' DIA. SANITARY SEWER MANHOLE	EA	1		
852	EXTRA DEPTH MANHOLE	VF	3.4		
855	RECONSTRUCTION OF EXISTING MANHOLES	EA	2		
SP864-S2	BYPASS PUMPING (LARGE DIAMETER SANITARY SEWERS)	EA	1		
866	SEWER MAIN TELEVISION INSPECTION (8" TO 24")	LF	3426		
866	SEWER MAIN TELEVISION INSPECTION (27" AND LARGER)	LF	314		
SP901.1	INSTALL CIPP SANITARY SEWER PIPE (HOT WATER) (24")	LF	3426		
SP901.2	INSTALL CIPP SANITARY SEWER PIPE (HOT WATER) (30")	LF	314		
SS910.1	MANHOLE REHABILITATION (STANDARD MANHOLES UP TO 5'	VF	109.1		
	DIA.)	CAL			
SS910.3	URETHANE GROUT INJECTION	GAL	20		
SS1020	GOLF COURSE RESTORATION ALLOWANCE	ALW	1		
SP1103.1	POINT REPAIRS FOR 24" DIAMETER (6'-10' DEPTH)	EA	9		
SP1103.2	POINT REPAIRS FOR 24" DIAMETER (10'-14' DEPTH)	EA	7		
SP1103.3	EXTRA LENGTH POINT REPAIRS FOR 24" DIAMETER (6'-10' DEPTH)	LF	72		
SP1103.4	EXTRA LENGTH POINT REPAIRS FOR 24" DIAMETER (10'-14' DEPTH)	LF	80		
SP1103.5	OBSTRUCTION REMOVAL BY REMOTE DEVICE, 21" OR 24" DIAMETER, ALL DEPTHS	EA	11		
SS7003.1	CONSTRUCTION SAFETY FENCING	LF	2305		
SS7003.2	TEMPORARY CHAIN LINK FENCE	LF	495		
SS9999	PROTECTIVE MATS	SY	6948		
		, ,,	05.0		

SP = SPECIAL PROVISION TO STANDARD SPECIFICATION. REFER TO CONTRACT DOCUMENTS FOR

SS = SPECIAL SPECIFICATION.
REFER TO CONTRACT DOCUMENTS
FOR DETAILS.

100% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583

K·FRIESE + ASSOCIATES

PUBLIC PROJECT ENGINEE
10001 Reunion Place
Suite 404
Son Antonio, Texas 78216
P 210.491.2391 F 512.338.1784
TBPE Firm Number 6535
www.kfriee.com

THIS DOCUMENT IS NOT INTENDED FOR BIDDING.PERMITTING AND/OR CONSTRUCTION PURPOSES 100% SUBMITTAL

7/17/2019


No.	Revision	Drawn	Approved	Date
	REVI	SIONS		


SECT. No. DR. MW CK.


SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE


PROJECT SPECIFIC NOTES AND QUANTITIES


DEVELOPER:		
CONT.	BUDGET PROJ.	
SUBMITTED		
APPROVED		
MAP No.		SHEE

































- PROPOSED BYPASS ROUTE LINE TO BE REHABILITATED BY CIPP 24" WW ---- EXISTING SANITARY SEWER LINE ----- 100-YEAR FLOODPLAIN

BYPASS FLOW DATA

SUCTIO	ON ME	53357
SIZE	24	INCHES
ADWF	3.2	MGD
PDWF	4.3	MGD
PWWF	7.1	MGD





THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583
7/17/2019
THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

90% SUBMITTAL



No.	Rev	ision	Drawn	Approved	Date
	•	REVI	SIONS		
		SILVERH 24-INCI OVERAI		OLF COAB PAC	

EVELOPER:			
CONT.	BUDGET	PROJ.	
SUBMITTED			
APPROVED			
MAP NO			SHEET

SECT. No. DR. MW CK. JOB No. 18-4540 OF 45

K.FRIESE + ASSOCIATES PUBLIC PROJECT ENGINEERING



- CONTRACTOR MUST NOTIFY AND/OR CONTACT SAWS INSPECTION AT 210-233-3500 48 HOURS BEFORE ANY OF THE FOLLOWING ACTIVITIES TAKE PLACE:
 - NOTIFICATION OF PRE-TELEVISION INSPECTION NOTIFICATION OF BYPASS PUMPING SETUP OPERATIONS NOTICICATION OF THE PIPE INSTALLATION
- CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCES, PIPE SIZES, AND GRADES BEFORE START OF CONSTRUCTION.
- BYPASS PIPING SHALL BE BURIED AT CROSSINGS WITH GOLF CART PATH IN ORDER TO MAINTAIN TRAFFIC.
- 4. EXISTING UTILITIES ARE NOT SHOWN FOR CLARITY. CONTRACTOR RESPONSIBLE FOR CALLING IN LOCATES AND SHALL EXERCISE CAUTION IN AREAS OF EXCAVATION.
- FLOWS FOR LINES 24" AND GREATER WERE PROVIDED BY SAWS. FLOWS FOR SMALL DIAMETER LINES ARE TO BE DETERMINED BY CONTRACTOR PER SPECIFICATION
- CONTRACTOR SHALL CONTACT THE FOLLOWING TO COORDINATE WORK AT THE PROJECT SITE:
 - SILVERHORN: SARA:
- MR. NEIL THRAILKILL AT 210-495-1689
 MR. JOSHUA SPENCER AT 210-302-3237
 MS. SARAH ESPINOZA AT 210-374-1945
 MR. MIKE RODRIGUEZ AT 210-379-7088
 MR. JOE IBARRA AT 210-844-8317 (CELL)
 210-615-6334 (OFFICE)
- D. TXDOT INSPECTOR:
- SEWER BYPASS PIPE ROUTED THROUGH CULVERTS SHALL CONSIST OF HDPE PIPE (DR 17 MINIMUM). PIPING SHALL EXCEED MINIMUM REQUIREMENTS WHERE NEEDED TO MEET DISCHAGE PRESSURE IN CONTRACTOR'S APPROVED BYPASS PLAN.

EXISTING FIRE HYDRANT WASTEWATER LINE TO BE REHABILITATED

PROPERTY LINE

----- 100-YEAR FLOODPLAIN LIMITS · - - -

CONCEPTUAL BYPASS LINE



PRIMARY CONSTRUCTION ACCESS

SECONDARY CONSTRUCTION ACCESS



100% SUBMITTAL

K·FRIESE + ASSOCIATES

PUBLIC PROJECT ENGINEE 10001 Reunion Place Suite 404 San Antonio, Texas 78216 P 210.491.2391 F 512.338.1784 IBPE Firm Number 6535 www.kfriese.com

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN,P.E. 96583

7/17/2019 THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL

No.	Revision	Drawn	Approved	Date	
	REVISIONS				



SECT. No.


SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE

PROPOSED BYPASS PLAN

(1 OF 5)

DEVELOPER:		
CONT.	BUDGET PROJ.	i
SUBMITTED_		
APPROVED _		
MAP No.		SHEET

DR. MW CK.




- CONTRACTOR MUST NOTIFY AND/OR CONTACT SAWS INSPECTION AT 210-233-3500 48 HOURS BEFORE ANY OF THE FOLLOWING ACTIVITIES TAKE PLACE:
 - NOTIFICATION OF PRE-TELEVISION INSPECTION NOTIFICATION OF BYPASS PUMPING SETUP OPERATIONS NOTICICATION OF THE PIPE INSTALLATION
- CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCES, PIPE SIZES, AND GRADES BEFORE START OF CONSTRUCTION.
- BYPASS PIPING SHALL BE BURIED AT CROSSINGS WITH GOLF CART PATH IN ORDER TO MAINTAIN TRAFFIC.
- 4. EXISTING UTILITIES ARE NOT SHOWN FOR CLARITY. CONTRACTOR RESPONSIBLE FOR CALLING IN LOCATES AND SHALL EXERCISE CAUTION IN AREAS OF EXCAVATION.
- FLOWS FOR LINES 24" AND GREATER WERE PROVIDED BY SAWS. FLOWS FOR SMALL DIAMETER LINES ARE TO BE DETERMINED BY CONTRACTOR PER SPECIFICATION
- CONTRACTOR SHALL CONTACT THE FOLLOWING TO COORDINATE WORK AT THE PROJECT SITE:

 - C. PARK AT WEST AVE:
- MR. NEIL THRAILKILL AT 210-495-1689 MR. JOSHUA SPENCER AT 210-302-3237 MS. SARAH ESPINOZA AT 210-374-1945 MR. MIKE RODRIGUEZ AT 210-379-7088

EXISTING FIRE HYDRANT WASTEWATER LINE TO BE REHABILITATED -x" ww- EXIST WASTEWATER LINE PROPERTY LINE ----- 100-YEAR FLOODPLAIN LIMITS

LEGEND



PRIMARY CONSTRUCTION ACCESS

SECONDARY CONSTRUCTION ACCESS




100% SUBMITTAL

K·FRIESE + ASSOCIATES PUBLIC PROJECT ENGINEER
10001 Reunion Place
Suite 404
Son Antonio, Texas 78216
P 210.491.2391 F 512.338.1784
IBPE Firm Number 6535
www.kfriese.com

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583 7/17/2019 THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL





SECT. No.


SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE

PROPOSED BYPASS PLAN

(2 OF 5)

DEVELOPER:			
CONT.	BUDGET	PROJ.	
SUBMITTED_			
APPROVED _			
MAP No.			SHEET

DR. MW CK.





SHEET

JOB No. 18-4540 OF 45

DR. MW CK.



- CONTRACTOR MUST NOTIFY AND/OR CONTACT SAWS INSPECTION AT 210-233-3500 48 HOURS BEFORE ANY OF THE FOLLOWING ACTIVITIES TAKE PLACE:
 - NOTIFICATION OF PRE-TELEVISION INSPECTION NOTIFICATION OF BYPASS PUMPING SETUP OPERATIONS NOTICICATION OF THE PIPE INSTALLATION
- CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCES, PIPE SIZES, AND GRADES BEFORE START OF CONSTRUCTION.
- BYPASS PIPING SHALL BE BURIED AT CROSSINGS WITH GOLF CART PATH IN ORDER TO MAINTAIN TRAFFIC.
- 4. EXISTING UTILITIES ARE NOT SHOWN FOR CLARITY. CONTRACTOR RESPONSIBLE FOR CALLING IN LOCATES AND SHALL EXERCISE CAUTION IN AREAS OF EXCAVATION.
- FLOWS FOR LINES 24" AND GREATER WERE PROVIDED BY SAWS. FLOWS FOR SMALL DIAMETER LINES ARE TO BE DETERMINED BY CONTRACTOR PER SPECIFICATION
- 6. CONTRACTOR SHALL CONTACT THE FOLLOWING TO COORDINATE WORK AT THE PROJECT SITE:

MR. NEIL THRAILKILL AT 210-495-1689 MR. JOSHUA SPENCER AT 210-302-3237

7. CONTRACTOR SHALL SECURE BYPASS PUMPING EQUIPMENT WITH SCREENED 6' TALL CHAIN LINK FENCE.

BYPASS FLOW DATA

SUCTION MH 53357				
SIZE	24	INCHES		
ADWF	3.2	MGD		
PDWF	4.3	MGD		
PWWF	7.1	MGD		

LEGEND

EXISTING FIRE HYDRANT
WASTEWATER LINE TO BE REHABILITATED

----- 100-YEAR FLOODPLAIN LIMITS

· - - -

CONCEPTUAL BYPASS LINE

PRIMARY CONSTRUCTION ACCESS

SECONDARY CONSTRUCTION ACCESS



100% SUBMITTAL

K·FRIESE + ASSOCIATES

PUBLIC PROJECT ENGINEE

10001 Reunion Place
Suite 404
San Antonio, Texas 78216
P 210.491.2391 F 512.338.1784
IBPE Firm Number 6535
www.kfrises.com

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN,P.E. 96583

7/17/2019 THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL

No.	Revision	Drawn	Approved	Date
REVISIONS				





SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE

PROPOSED BYPASS PLAN

(5 OF 5)

DEVELOPE	R:			
CONT.		BUDGET	PROJ.	
SUBMITTE	D			
APPROVED				
MAP No.				SHEET
SECT. No.				21
DR. MW	CK.	JOB No.	18-4540	OF 45






CONSTRUCTION ACCESS TYPICAL DETAIL - HOLE 1 N.T.S.

- NOTES:
 1. CONTRACTOR TO SELECT ROUTE TO
 MINIMIZE CLEARING. SEE NOTE 3 UNDER
 GOLF COURSE NOTES (SHEET 3).
 2. CONTRACTOR SHALL STAKE THE EDGES OF
 THE 30-FOOT PRIMARY ACCESS ROUTE AT
 50-FOOT INTERVALS USING SURVEY LATH
 OR EQUIVALENT PRIOR TO CLEARING.
 3. CONTRACTOR SHALL COODINATE WITH SAWS
 AND SILVERHORN GOLF COURSE TO
 SCHEDULE A WALK THROUGH FOR APPROVAL
 OF THE STAKED PRIMARY ACCESS AREA
 PRIOR TO CLEARING THE ACCESS AREA.

LEGEND




PRIMARY ACCESS ROUTE

SECONDARY CONSTRUCTION ACCESS ROUTE

LINE TO BE REHABILITATED BY CIPP EXISTING SANITARY SEWER LINE ----- 100-YEAR FLOODPLAIN

- NOTES:
 1. REFER TO GOLF COURSE NOTE 2 (SHEET 3)
 FOR ACCESS ROUTE INTENT.
 2. REFER TO SHEETS 24 31 FOR ACCESS
 AND RESTORATION DETAILS.
 3. REFER TO SHEETS 32 39 FOR TREE
 REMOVAL AND PRESERVATION DETAILS.





90% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM. REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583
7/17/2019

THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

90% SUBMITTAL



No.	Rev	ision	Drawn	Approved	Date
	REVISIONS				




DR. MW CK.


SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE


JOB No. 18-4540 OF 45


OVERALL ACCESS ROUTE


DEVELOPER:		
CONT.	BUDGET PROJ.	
SUBMITTED_ APPROVED _		
MAP No.		SHEE

















	ESTIMATED QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	QUANTITY		
SP164.1	CELLULOSE FIBER MULCH SEEDING (PERM) (TXDOT SPEC)	SY	2130		
515	TOPSOIL (4" THICK)	SY	64		
516.1	BERMUDA SODDING (COSA SPEC)	SY	64		



HYDROMUL CH I NG

DRILL SEEDING




SODDING AND TOPSOIL



CONCRETE REPLACEMENT



PROTECTIVE MATTING



SECONDARY CONSTRUCTION ACCESS
WASTEWATER LINE TO BE REHABILITATED ----x" ww--- EXIST WASTEWATER LINE

PROPERTY LINE
100-YEAR FLOODPLAIN LIMITS

TEMPORARY CHAIN LINK FENCE
CONSTRUCTION SAFETY FENCE



100% SUBMITTAL



THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM. REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 99653. 7/17/2019

THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL

				·		
				·		
No.	Revision	Drawn	Approved	Date		
	DEVICEOUS					

REVISIONS





DR. MW CK.


SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE


GOLF COURSE ACCESS AND RESTORATION (7 OF 8)


DEVELOPER:		
CONT.	BUDGET PROJ.	
SUBMITTEDAPPROVED		
MAP No.		SHEET
SECT. No.		□ 30



















PROPERTY LINE

100-YEAR FLOODPLAIN LIMITS
30 FT RIPARIAN BUFFER

PRIMARY CONSTRUCTION ACCESS

SECONDARY CONSTRUCTION ACCESS

TREE CANOPY TO BE REMOVED
(IN FLOODPLAIN)

TREE CANOPY TO REMAIN
(IN FLOODPLAIN)

TREE CANOPY TO BE REMOVED
(IN 30 FT RIPARIAN BUFFER)

TREE CANOPY TO REMAIN
(IN 30 FT RIPARIAN BUFFER)

TREE CANOPY TO BE REMOVED
(NOT IN FLOODPLAIN)

TREE CANOPY TO BE REMOVED
(NOT IN FLOODPLAIN)

NOTE:

 REFER TO PROJECT SPECIFIC NOTES ON SHEET 3 AND DETAIL ON SHEET 23 FOR LIMITS OF CLEARING.



0 30'

K.FRIESE + ASSOCIATES PUBLIC PROJECT ENGINEERING

+ ASSOCIA

PUBLIC PROJECT ENGIL

10001 Reunion Place
Suite 404
San Antonio, Texas 78216
P 210.491.2391 F 512.338.178

IBPE Firm Number 6535
www.kfrises.com

100% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM. REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583
7/17/2019

THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

100% SUBMITTAL

No.	Revision	Drawn	Approved	Date		
	REVISIONS					



DR. MW CK.

SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE


TREE CANOPY ASSESSMENT


(7 OF 8)

JOB No. 18-4540 OF 45

DEVELOPER:		
CONT.	BUDGET PROJ.	
SUBMITTED		
APPROVED		
MAP No.		SHEE
SECT. No.		ີ 38

ir igledisioooo - GAVVO oliveiiidii rackageliddivoileetsioooo _ i NEEC _ o'i agii iildaliied by alisciel dii 777/2013





NOT FOR CONSTRUCTION FOR INFORMATION ONLY

NOT TO SCALE



10001 Reunion Place Suite 404 San Antonio, Texas 78216 P 210.491.2391 F 512.338.1784 TBPE Firm Number 6535 www.kfriese.com

No. Revision Drawn Approved Date
REVISIONS


APPROVED


SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE


> AS-BUILT MH 53151 AND MH 52919

DEVELOPER:
CONT. BUDGET PROJ.
SUBMITTED______


MAP No. SHEET 40
DR. CK. JOB No. 18-4540 OF 45







MH 52992 RECONSTRUCTION - TOP VIEW SCALE: NTS



PLYWOOD PROTECTION DETAIL SCALE: NTS

100% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERM. REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583
7/17/2019
THIS DOCUMENT IS NOT INTENDED FOR BIDDING, PERMITTING AND/OR CONSTRUCTION PURPOSES

K+FRIESE + ASSOCIATES PUBLIC PROJECT ENGINEERING Reunion Place

100% SUBMITTAL

No.	Revision	Drawn	Approved	Date	
	REVISIONS				



CK.

DR.

SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE

DETAILS


JOB No. 18-4540 OF 45

SITE DESCRIPTION EROSION AND SEDIMENTATION CONTROLS OTHER EROSION AND SEDIMENTATION CONTROLS PROJECT NAME AND LOCATION: 2019 SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE (SAWS JOB NO.18-4540) SOIL STABILIZATION PRACTICES: THIS PROJECT CONSISTS OF 2 DIFFERENT PROJECT LOCATIONS LOCATED ON AND NEAR THE SILVERHORN GOLF HYDROMULCHING ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER. IF A REPAIR IS NECESSARY, IT WILL BE DONE AT THE EARLIEST DATE POSSIBLE, BUT NO LATER THAN 7 CALENDAR DAYS AFTER THE SURROUNDING EXPOSED GROUND HAS DRIED SUFFICIENTLY TO PREVENT FURTHER DAMAGE FROM HEAVY EQUIPMENT. THE AREAS ADJACENT TO CREEKS AND DRAINAGEWAYS SHALL HAVE PRIORITY, FOLLOWED BY DEVICES PROTECTING STORM SEWER INLETS. COURSE IN THE CITY OF SAN ANTONIO TEMPORARY SEEDING PERMANENT PLANTING, SODDING OR SEEDING MULCHING INSPECTION: SOIL RETENTION BLANKET AN INSPECTION WILL BE PERFORMED BY THE CONTRACTOR EVERY 14 DAYS AS WELL AS AFTER EVERY 1/2" OR MORE AN INSPECTION WILL BE PERFORMED BY ITE CONTINUED TO SEE THE CONTROLLED AT THE PROJECT SITE, AN INSPECTION AND OF FAIN (RECORDED ON A NON-PREZING RAIN GAIGE TO BE LOCATED AT THE PROJECT SITE, AN INSPECTION AND MAINTENANCE REPORT WILL BE MADE PER INSPECTION, BASED ON THE INSPECTION RESULTS, THE CONTROLS SHALL BE CORRECTED BEFORE THE NEXT SCHEDULED INSPECTION. BUFFER ZONES PRESERVATION OF NATURAL RESOURSES CONTACT AND PHONE NO.: (CONTRACTOR) OTHER: ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL STATE AND LOCAL CITY SOLID WASTE MANAGEMENT REGULATIONS, ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED AS NECESSARY OR AS REGULATION BY LOCAL REGULATION AND THE DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITY HAS CEASED TEMPORARILY OR PERMANENTLY, SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITIES ARE SCHEDULED TO RESUME AND DONE WITHIN 21 DAYS. PROJECT DESCRIPTION: THIS PROJECT IS A LARGE DIAMETER SANITARY SEWER REHABILITATION PROJECT WITH TRASH WILL BE HAULED TO A LOCAL DUMP, NO CONSTRUCTION MATERIALS WILL BE BURIED ON SITE, PIPE SIZES RANGING FROM 24" TO 30" IN DIAMETER. THERE IS A TOTAL OF 3,741 LF OF SEWER BEING STRUCTURAL PRACTICES: HAZARDOUS WASTE (INCLUDING SPILL REPORTING): REHABILITATED USING CURED-IN-PLACE PIPE (CIPP) ___SILT FENCES AT A MINIMUM, ANY PRODUCTS IN THE FOLLOWING CATEGORIES ARE CONSIDERED TO BE HAZARDOUS: PAINTS, HAY BALES AT A WINNIOUS WIT PRODUCT IN THE POLICIAMING ACIDS FOR CLEANING SOLVENTS, ASPHALT PRODUCTS, CHEMICAL ADDITIVES FOR SOLID STABILIZATION OR CONCRETE CUBING COMPOUNDS AND ADDITIVES. IN THE EVENT OF A SPILL WHICH MAY BE HAZARDOUS AND METIS REPORTING REQUIREMENTS, THE NATIONAL RESPONSE CENTER SHOULD BE CONTACTED AT 800-424-8802, AND ANY REQUIRED CHANGES MADE TO THE SWPPP, IN THE EVENT OF A LIFE THREATENING SPILL THE SAN ANYONIO FIRE DEPARTMENT SHOULD BE NOTIFIED AS WELLOW. ___GRAVEL FILTRATION BAGS __ROCK BERMS __DIVERSION, INTERCEPTOR OR PERIMETER DIKES AS THE APPROPRIATE CITY INSPECTORS. __DIVERSION, INTERCEPTOR OR PERIMETER SWALES DIVERSION, DIKE AND SWALE COMBINATIONS SANITARY WASTE ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS AS NECESSARY OR AS REQUIRED BY ROCK BEDDING AT CONSTRUCTION EXIT (STABILIZED ENTRANCE) LOCAL REGULATION BY A LICENSED SANITARY SEWER WASTE MANAGEMENT COMPANY. PORTABLE UNITS SHALL NOT BE MAJOR SOIL DISTURBING ACTIVITIES: SOIL DISTURBANCE ACTIVITIES WILL INCLUDE PREPARING EASEMENT AREA AND ___TIMBER MATTING AT CONSTRUCTION EXIT (STABILIZED ENTRANCE) _____ CHANNEL LINERS LOCATED WITHIN THE FLOODPLAIN. RIGHT-OF-WAYS, CLEARING AND GRUBBING, TRENCHING, POINT REPAIR AREAS, EROSION AND SEDIMENT CONTROLS, AND TOPSOIL WORK FOR FINAL SEEDING AND SODDING ____SEDIMENT BASINS OFFSITE EXCAVATION SOURCE LOCATION NOT APPLICABLE ___STORM INLET SEDIMENT TRAP ___STONE OUTLET SEDIMENT STRUCTURES CURBS AND GUTTERS ___STORM SEWERS -VELOCITY CONTROL STRUCTURES OFFSITE FILL SOURCE LOCATION NOT APPLICABLE ___GEOTEXTILES OTHER: NOT APPLICABLE OFFSITE VEHICLE TRACKING NOT APPLICABLE TOTAL PROJECT AREA (ACRES): APPROX 6.11 ACRE NARRATIVE - SEQUENCE OF CONSTRUCTION TOTAL AREA TO BE DISTURBED: APPROX 0.66 ACRE (STORMWATER MANAGEMENT) ACTIVITIES: THE ORDER OF ACTIVITIES WILL BE AS FOLLOWS: INSTALL SEDIMENT CONTROL FENCES, ROCK BERMS, FILTRATION HAUL ROADS DAMPENED FOR DUST CONTROL. ▲ LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN WEIGHTED RUNOFF COEFFICIENT: (AFTER CONSTRUCTION) NOT APPLICABLE BAGS AND CONSTRUCTION EXITS. PREPARE EASEMENT AREA BY CLEARING AND GRUBBING OF EXCESS DIRT ON ROAD TO BE REMOVED DAILY VEGETATION AND TREES AS PER TREE PERMIT REQUIREMENTS. REMOVE /INSTALL /ADJUST TEMPORARY STABILIZED CONSTRUCTION ENTRANCE. EROSION, SEDIMENT, AND STORM WATER POLLUTION CONTROL MEASURES. SITE CLEANUP AND VARIES BY PROJECT LOCATION REVEGETATION OF DISTURBED AREAS. REMOVAL OF TEMPORARY CONTROL DEVICES. A DESCRIPTION OF MAINTENANCE CERTIFICATION THAT SITE DISTURBANCE AND / OR DISCHARGES WILL NOT EFFECT LISTED ENDANGERED SPECIES PROCEDURES FOR CONTROL MEASURES USED: DISTURBED AREAS THAT ARE EXPOSED TO WHAT METHOD IS USED TO SATISFY THE ENDANGERED SPECIES REQUIREMENTS? ___NOT APPLICABLE PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF POLLUTANTS ENTERING THE CREEK SYSTEMS. DESCRIPTION OF WATER DISCHARGED NOT ASSOCIATED WITH CONSTRUCTION: DISCHARGES FROM FIRE FIGHTING ACTIVITIES OR LOCATIONS WHERE VEHICLE AND EQUIPMENT ENTER, EXIT OR TRAVEL THROUGH THE SITE SHALL BE FIRE HYDRANT FLUSHING, WATER TO CONTROL DUST, UNCONTAMINATED GROUNDWATER OR ACCUMULATED INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT TRACKING, CONTRACTOR SHALL PROVIDE CONTROL STORMWATER MEASURES TO REPAIR/REPLACE APPURTENANCES AS NEEDED. DISPOSAL AREAS, STOCKPILES AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT ENTERS RECEIVING WATERS, DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WETLAND, BODY OF WATER, STREAMBED OR FLOODPLAIN CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED BY THE CONTRACTOR IN A MANNER TO MINIMIZE THE RUNOFF OF POLLUTANTS, ALL WATERWAYS SHALL BE CLEARED AS SOON AS POSSIBLE OF TEMPORARY EMBADIXMENT, TEMPORARY BRIDGES, MAITING, FALSEWORK, PLING DEBRIS OR OTHER OBSTRUCTION PLACED DURING CONSTRUCTION OPERATIONS THAT ARE NOT PART OF THE FINISHED WORK. NAME OF RECEIVING WATERS: VARIES BY PROJECT LOCATION STORMWATER MANAGEMENT: CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE TO EXISTING STORMWATER SYSTEMS, STORMWATER DISCHARGE SHALL BE CONVEYED THROUGH EXISTING STORM DRAIN SYSTEMS, CULVERTS, CHANNELS, NATURAL STREAMS, DITCHES, ETC. ALL DISTURBED AREAS SHALL BE IDENTIFY STORMWATER DISCHARGE POINTS: VARIES BY PROJECT LOCATION RESTORED TO PRE-CONSTRUCTION CONDITIONS. CITY OF SAN ANTONIO A DESCRIPTION OF PERMANENT STORM WATER MANAGEMENT CONTROLS: NOT APPLICABLE CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT A DESCRIPTION AND TIME FRAME FOR INSTALLATION OF STABILIZATION PRACTICES IN CONJUNCTION WITH CONSTRUCTION: SITES SHALL BE STABILIZED UPON COMPLETION OF SEWER CONSTRUCTION ACTIVITIES

STORM WATER POLLUTION PREVENTION PLAN (SWP3) NARRATIVE

JANUARY 2005

% SUBMITTAL PROJECT NO.



GRAVEL FILTERS CAN BE USED ON PAVEMENT OR BARE GROUND.

CURB INLET GRAVEL FILTER

SCALE: $1^\circ = 5^\circ$


GRAVEL FILTER BAGS

SCALE : 1" = 5'

WATER POLLUTION CONTROL

MEASURES STANDARDS 1

% SUBMITTAL PROJECT NO.:



WASHOUT PIT GENERAL NOTES:

DETAILS ILLUSTRATE MINIMUM DIMENSIONS, PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.

IF HAY BALES ARE USED FOR BERM, THEY SHALL BE ANCHORED IN PLACE WITH 2 REBARS PER BALE, DRIVEN L INTO GROUND ENOUGH TO PROVIDE REASONABLE STABILITY.

WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC.

WASHOUT PIT SHALL NOT BE LOCATED IN AREA SUBJECT TO INUNDATION FROM STORM WATER RUNOFF.

PIT SHALL NOT BE LOCATED OVER OR IN THE IMMEDIATE VICINITY OF A FEATURE OF GROUNDWATER RECHARGE.

ROCK FILTER DAM USAGE GUIDELINES

ROCK FILTER DAMS SHOULD BE CONSTRUCTED DOWNSTREAM FROM DISTURBED AREAS TO INTERCEPT SEDIMENT FROM OVERLOAD RUNOFF AND /OR CONCENTRATED FLOW. THE DAMS SHOULD BE SIZED TO FILTER A MAXIMUM FLOW THRU RATE OF 60 GPM /FT SQUARED OF CROSS SECTIONAL AREA., A 2 YEAR STORM FREQUENCY MAY BE USED TO CALCULATE THE FLOW RATE.

TYPE 1 (18" HIGH WITH NO WIRE MESH) :

TYPE 1 MAY BE USED AT THE TOE OF SLOPES, AROUND INLETS, IN SMALL DITCHES AND AT DIKE OR SWALE OUTLETS. THIS TYPE OF DAM IS RECOMMENDED TO CONTROL EROSION FROM A DRAINAGE AREA OF 5 ACRES OR LESS. TYPE 1 MAY NOT BE USED IN CONCENTRATED HIGH VELOCITY FLOWS (APPROXIMATELY 8 FT./SEC, OR MORE) IN WHICH AGGREGATE WASH OUT MAY OCCUR. SANDBAGS MAY BE USED AT THE EMBEDDED FOUNDATION (4" DEEP MIN.) FOR BETTER FILTERING EFFICIENCY OF LOW FLOWS IF CALLED FOR ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

TYPE 2 (18" HIGH WITH WIRE MESH);

TYPE 2 MAY BE USED IN DITCHES AND AT DIKE OR SWALE OUTLETS

TYPE 3 (36" HIGH WITH WIRE MESH)

TYPE 3 MAY BE USED IN STREAM FLOW AND SHOULD BE SECURED TO THE STREAM BED.

TYPE 4 (SACK GABIONS):

TYPE 4 MAY BE USED IN DITCHES AND SMALLER CHANNELS TO FORM AN EROSION CONTROL DAM.


GENERAL NOTES

- 1. IF SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER, FILTER DAMS SHOULD BE PLACED NEAR THE TOE OF SLOPES WHERE EROSION IS ANTICIPATED, UPSTREAM AND / OR DOWNSTREAM AT DRAINAGE STRUCTURES, AND IN ROADWAY DITCHES AND CHANNELS TO COLLECT SEDIMENT.
- MATERIALS (AGGREGATE, WIRE MESH, SANDBAGS, ETC.) SHALL BE AS INDICATED BY THE SPECIFICATION FOR ROCK FILTER DAMS FOR EROSION AND SEDIMENTATION CONTROL.
- 3. THE ROCK FILTER DAM DIMENSIONS SHALL BE AS INDICATED ON THE STORM WATER POLLUTION PREVENTION PLANS.
- 4. SIDE SLOPES SHOULD BE 2:10R FLATTER, DAMS WITHIN THE SAFETY ZONE SHALL HAVE SIDE SLOPES OF 6:10R FLATTER.
- 5. MAINTAIN A MINIMUM OF 1' BETWEEN TOP OF ROCK FILTER DAM WEIR AND TOP OF EMBANKMENT FOR FILTER DAMS AT SEDIMENT TRAPS.
- 6. FILTER DAMS SHOULD BE EMBEDDED A MINIMUM OF 4" INTO THE EXISTING GROUND,
- 7. THE SEDIMENT TRAP FOR PONDING OF SEDIMENT LADEN RUNOFF SHALL BE OF THE DIMENSIONS SHOWN ON THE PLANS.
- 8. ROCK FILTER DAM TYPES 2 & 3 SHALL BE SECURED WITH 20 GAUGE GALVANIZED WOVEN WIRE MESH WITH 1" DIAMETER HEXAGONAL OPENINGS. THE AGGREGATE SHALL BE PLACED ON THE MESH TO THE HEIGHT AND SLOPES SPECIFIED. THE MESH SHALL BE FOLDED AT THE UPSTREAM SIDE OVER THE AGGREGATE AND TIGHTLY SECURED TO ITSELF ON THE DOWNSTREAM SIDE USING WIRE TIES OR HOG RINGS. IN STREAM USE, THE MESH SHOULD BE SECURED OR STAKED TO THE STREAM BED PRIOR TO AGGREGATE PLACEMENT.
- 9. SACK GABIONS SHOULD BE STAKED DOWN WITH 3 /4" DIA. REBAR STAKES.
- 10. FLOW OUTLET SHOULD BE ONTO A STABILIZED AREA (VEGETATION, ROCK, ETC.).
- 11. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.

JANUARY 2005

CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

TEMPORARY EROSION, SEDIMENT & WATER POLLUTION CONTROL



ESTABLISH FENCE PROTECTION MINIMUM 5' FROM TRUNK

ROOT PROTECTION

DRIP LINE

N. T. S.

12" MIN

1. ALL THE TREES WITH A DIAMETER GREATER THAN 3 INCHES AFFECTED BY CONSTRUCTION SHALL HAVE THE LIMBS AND ROOTS TRIMMED AND PRUNED ACCORDING TO ITEM No. 802 TREE PRUNING, SOIL AMENDING AND FERTILIZATION, UNLESS SPECIFIED TREES SHALL RECEIVE LEVEL 2 PROTECTION AS PER ITEM No. 802 ARE SHOWN ON TREE PROTECTION TABLE ON THIS SHEET.

- 2. ALL TREES SHALL REMAIN UNLESS NOTED ON THE PLANS.
- 3. NO SITE PREPARATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND APPROVED.
- 1. TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING SITE CONSTRUCTION.

5. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN THREE INCHES IN DIAMETER WHEN EXCAVATION NEAR EXISTING TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR.

6. THE ROOT PROTECTION ZONE IS THAT AREA SURROUNDING A TREE, AS MEASURED BY A RADIUS FROM THE TREE TRUNK, IN WHICH NO EQUIPMENT, VEHICLES OR MATERIALS MAY OPERATE OR BE STORED THE REQUIRED RADIUS LENGTH IS 1 FOOT PER DIAMETER INCH OF THE TREE. FOR EXAMPLE, A 1C-INCH DIAMETER TREE WOULD HAVE A 5-FOOT RADIUS ROOT PROTECTION ZONE AROUND THE TREE. ROOTS OR BRANCHES THAT ARE IN COMPILICT WITH THE CONSTRUCTION SHALL BE CUIT CLEANLY ACCORDING TO PROPER PRUNING METHODS. LIVE OAK WOUNDS SHALL BE PAINTED OVER, WITHIN 20 MINUTES TO PREVENT OAK WILT.

- 7. ACCESS TO FENCED AREAS WILL BE PERMITTED ONLY WITH THE APPROVAL OF THE ENGINEER OR CITY INSPECTOR.
- 8. GRADING, IF REQUIRED, SHALL BE LIMITED TO A 3 INCH CUT OR FILL WITHIN THE FENCED ROOT ZONE AREAS.
- 9. TREES, SHRUBS OR BUSHES TO BE CLEARED FROM PROTECTED ROOT ZONE AREAS SHALL BE REMOVED BY HAND AS DIRECTED BY THE PROJECT MANAGER OR CITY INSPECTOR.
- 10. TREES DAMAGED OR LOST DUE TO CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE ENGINEER'S SATISFACTION.
- 11. EXPOSED ROOTS SHALL BE COVERED AT THE END OF EACH DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH OR WET BURLAP.
- 12. ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST PRIOR TO ITS REMOVAL.

GENERAL NOTES

100% SUBMITTAL

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM, REVIEW UNDER THE AUTHORITY OF MICHAEL PERSYN, P.E. 96583

K·FRIESE + ASSOCIATES

7/17/2019 THIS DOCUMENT IS NOT INTENDED FOR BIDDING.PERMITTING AND/OR PUBLIC PROJECT ENGINEE
10001 Reunion Place
Suite 404
San Antonio, Texas 78216
P 210.491.2391 F 512.338.1784
TBPE Firm Number 6535
waw k friese com CONSTRUCTION PURPOSES

100% SUBMITTAL


No.	Revision	Drawn	Approved	Date

REVISIONS SILVERHORN GOLF COURSE 24-INCH REHAB PACKAGE

> TREE PROTECTION DETAILS

DEVELOPER: BUDGET PROJ. CONT. SUBMITTED APPROVED

MAP No. SHEET SECT. No. DR. MW CK. JOB No. 18-4540 OF 45



BRANCH CLEARANCE DETAIL