HISTORIC AND DESIGN REVIEW COMMISSION October 16, 2019

HDRC CASE NO: 2019-573

ADDRESS: 119 ADAMS ST

LEGAL DESCRIPTION: NCB 931 BLK LOT 17 AND 18

ZONING: RM-4,HS, H

CITY COUNCIL DIST.: 1

DISTRICT: King William Historic District

LANDMARK: Koehler House

APPLICANT: Nicole Corwin/Tatanka
OWNER: Jarod and Celeste Oliver
TYPE OF WORK: Historic Tax Certification
APPLICATION RECEIVED: September 20, 2019

60-DAY REVIEW: November 19, 2019

CASE MANAGER: Huy Pham

REQUEST:

The applicant is requesting Historic Tax Certification for the property at 119 Adams St.

APPLICABLE CITATIONS:

Sec. 35-618. - Tax Exemption Qualifications.

- (a) Assessed Valuation. In accordance with the provisions of this article, a building, site, or structure which meets the definition of a historically significant site in need of tax relief to encourage preservation and which is substantially rehabilitated and/or restored as certified by the historic and design review commission and approved by the city tax assessor-collector, shall have an assessed value for ad valorem taxation as follows regardless of ownership during the granted time period:
 - (1) A residential property shall have the assessed value for ad valorem taxation for a period of ten (10) tax years equal to the assessed value prior to preservation.
- (b) Applicability. This exemption shall begin on the first day of the first tax year after verification of completion of the preservation required for certification; provided the building shall comply with the applicable zoning regulations for its use and location.
- (c) Application. Application for a historic structure preservation tax exemption pursuant to this division is to be filed with the office of historic preservation. The historic preservation officer shall be the agent of the city for the purposes of administering this division provided that the historic preservation officer request a recommendation from the historic and design review commission. Each application shall be signed and sworn to by the owner of the property and shall:
 - (1) State the legal description of the property proposed for certification;
 - (2) Include an affidavit by the owner describing the historic significance of the structure in need of tax relief;
 - (3) Include a final complete set of plans for the historic structure's restoration or rehabilitation;
 - (4) Include a statement of costs for the restoration or rehabilitation work;
 - (5) Include a projection of the estimated construction, time and predicted completion date of the historic restoration or rehabilitation;
 - (6) Authorize the members of the historic and design review commission, the city tax assessor-collector and city officials to visit and inspect the property proposed for certification and the records and books of the owners as necessary to certify that the property in question is in substantial need of restoration or rehabilitation;
 - (7) Include a detailed statement of the proposed use for the property; and
 - (8) Provide any additional information to the historic and design review commission which the owner deems relevant or useful such as the history of the structure or access to the structure by the public.

Each application shall contain sufficient documentation confirming or supporting the information submitted therein.

- (d) Certification.
 - (1) Historic and Design Review Commission Certification. Upon receipt of the owner's sworn application the

historic and design review commission shall make an investigation of the property and shall certify the facts to the city tax assessor-collector within thirty (30) days along with the historic and design review commission's documentation for recommendation of either approval or disapproval of the application for exemption.

- (2) Tax Assessor-Collector Approval. Upon receipt of the certified application for tax exemption as well as the recommendation of the historic and design review commission, the city's tax assessor-collector shall within thirty (30) days approve or disapprove eligibility of the property for tax relief pursuant to this division. In determining eligibility, the tax assessor-collector shall first determine that all the requirements of this division have been complied with and that only the historic structure and the land reasonably necessary for access and use thereof is to be provided favorable tax relief.
- (e) Verification of Completion. Upon completion of the restoration and rehabilitation, together with a fee as specified in Appendix "C" of this chapter, the owner, who may not be the same as at the time of application, shall submit a sworn statement of completion acknowledging that the historically significant site in need of tax relief to encourage preservation has been substantially rehabilitated or restored as certified by the historic and design review commission. The historic and design review commission, upon receipt of the sworn statement of completion, but no later than thirty (30) days thereafter, shall make an investigation of the property and shall recommend either approval or disapproval of the fact that the property has been substantially completed as required for certification. If the historic and design review commission recommends that it has not been substantially completed as so required, then the certified applicant may be required by the historic preservation officer to complete the restoration or rehabilitation in order to secure the tax exemption provided herein. If the verification of completion is favorable, the historic and design review commission shall recommend approval and the historic preservation office may notify the tax assessor-collector in writing of compliance. Thereafter, the tax assessor-collector shall provide the property with the historic tax exemption.
- (f) Historic Preservation Tax Exemptions.
 - (1) Historic Preservation Tax Exemption for Residences in Need of Substantial Repair. In accordance with the provisions of this chapter, a historically significant residential building, which meets both the definitions of a historically significant site in need of tax relief to encourage preservation and of a residential property in Appendix "A" of this chapter, and is either individually designated or is located within the boundaries of a locally designated historic district which is substantially rehabilitated and is approved by the chief appraiser of the Bexar County Appraisal District, shall have an assessed value for ad valorem taxation as follows:
 - A. A residential property shall have no assessed value for ad valorem taxation for a period of five (5) tax years after verification, as defined in Appendix "A" to this chapter. Thereafter, the exempt property shall be reappraised at current market value and assessed at a fifty (50) percent rate for an additional consecutive five-year period.
 - B. This exemption shall begin on the first day of the first tax year after verification of completion of the substantial rehabilitation by the historic and design review commission, provided compliance with subsection (b) of this section.
- (g) Eligibility.
- (1) The tax exemption options outlined in subsection (f), above, will remain in effect unless terminated by designation status being removed pursuant to subsection 35-606(g) of this article.

FINDINGS:


- a. The applicant is requesting Historic Tax Certification for 119 Adams located in the King William Historic District. Historic Tax Verification is also being heard for this property at the October 16, 2019, HDRC hearing.
- b. SCOPE OF APPROVED WORK A number of rehabilitative scopes of work have been approved including: exterior alterations to match historic elements, modification of an addition, and enclosure of a balcony. In addition to the previously noted exterior items, a number of interior scopes of work have been planned or completed including electrical, plumbing, and mechanical improvements, and interior finishes.
- c. TIMELINE OF COMPLETION The project began in July 2017, and was completed by October 2019.
- d. ITEMIZED LIST OF COST The applicant submitted an itemized list of costs that meets the threshold to be eligible for Historic Tax Certification.
- e. CERTIFICATION REQUIREMENT The requirements for Historic Tax Certification outlined in UDC Section 35-618 have been met and the applicant has provided evidence to that effect to the Historic Preservation Officer including photographs, an itemized list of costs, and a timeline for completion.

f. TAX INCENTIVE PERIOD - Approval of Tax Verification by the HDRC in 2019 means that the property owners will be eligible for the Substantial Rehabilitation Tax Incentive beginning in 2020.

RECOMMENDATION:

Staff recommends approval of Historic Tax Certification based on the findings b through f with the stipulation that all work is approved prior to Verification.

119 Adams



























Pre-Remodel Exterior, Front wood shutters to be repaired and replaces as needed, new paint throughout, wood railing & detailing to be repaired






Pre-Remodel Exterior, Northwest Corner wood shutters to be repaired and replaces as needed, new paint throughout, wood railing & deck to be repaired





Pre-Remodel Exterior, Southwest CornerWood deck and spa to be removed, 2nd floor to be added onto and balcony relocated. Leaded glass windows to be relocated..






Pre-Remodel 1st Kitchen

wall dividing kitchen from living to be removed, all new kitchen finishes, fixtures and cabinets.






Pre-Remodel 1st Mudroom/Laundry & Living reconfigure mudroom & laundry relocated, door to dining rm relocated & new cased opening to dining, relocated leaded windows.



Pre-Remodel 1st Powder Room to be reconfigured . all new finishes and fixtures








Pre-Remodel 2nd Floor Guest Bathroom B to receive new flooring and paint, restored and repair fixtures









Pre-Remodel Master Suite & BalconyNew layout and all new finishes and fixtures, doors to be reused

TATANKA Group Inc. Homestead General Contracting



Project Historic Rehabilitation Application

Location 119 Adams St. San Antonio, Tx 7821

Owner Jarod & Celeste Oliver

Representative Nicole Corwin tatankanicole@gmail.com Date 09/19/19

Rehabilitation Narrative & List of work performed

1 REMODEL & ADDITION

Approximately 3,000 SF of the existing home was remodeled. Much of the remodel affected the rear southwest and west of the building, an undocumented addition to the original Koehler House designed by Atlee Ayres in 1902.

- **a** Exterior—The exterior remodel included removal of an existing deck and spa, a new covered deck addition, window & door relocation and additions, southwest balcony layout modifications and new roofing addition.
 - I The new covered deck, located are the rear of the house in between the main house and the new accessory dwelling, is constructed of painted wood, synthetic decking and a multiwall polycarbonate roof. The deck serves as the new back entrance into the home.
 - All removed windows and doors were relocated throughout the remodel and new accessory dwelling. All new windows and doors are of wood construction and similar proportions to the originals.
 - **iii** The southwest balcony location was reoriented over the structure below to increase the 2nd floor master suite interior square footage. The modified balcony included new doors, new painted wood columns, railing, wood siding, wood decking with TPO underlayment and new electrical fixtures.
 - Iv The new galvalume standing seam hip roof addition was necessary to cover the modified balcony and master suite. The new standing seam is the same panel width as the original roofing.
- **b** Interior—The interior remodel included the 1st floor kitchen, living room, pantry, mudroom, powder room, and 2nd floor laundry room, guest baths and master suite. Careful attention was paid to respect finishes and character of the original home. Whenever possible materials were reused, newly installed materials were reclaimed, and non-reclaimed materials were selected for their longevity and sensitivity to the original materials. Poorly crafted or failing additions and modifications were removed.
 - The 1st floor remodel removed all failing undocumented additions. New foundation piers, structural joist, beams, decking, framing and columns were installed.
 - **ii** The 2nd floor interior remodel reconfigured an undocumented bathroom and closet remodel to become a new laundry room and new guest bathroom. Updated plumbing and flooring in the original bathroom. As well as modify an existing guest bedroom, bathroom and balcony to become the new master suite.
 - iii All non-original tile and soft wood flooring throughout the house was removed and replaced with reclaimed solid long leaf pine flooring, finger jointed into the original existing long leaf. All new long leaf pine door thresholds where made to match existing.

- iv All removed existing 6 panel wood doors where relocated throughout the remodel and accessory dwelling.
- **v** A combination of closed and open cell spray foam insulation was installed under the newly added and existing roof.
- c MEP— All the MEP systems throughout the house were upgraded.
 - i The HVAC system was upgraded, and the 1st floor supplies were relocated from furr downs in the ceiling to the floor.
 - ii All nob & tube electrical wiring was removed and replaced with Romex. All original electrical fixtures remained, and new electrical fixtures added.
 - **iii** All existing plumbing lines affected by the remodel were replaced with PEX. There were no original historic plumbing fixtures in the areas of the remodel, so new fixtures were selected throughout.

2 NEW CONSTRUCTION

A 1200 SF, 2 story accessory dwelling and garage located at the rear setback of the property; 600 SF 1^{st} floor with a 2-car garage and storage and 600 SF 2^{nd} floor conditioned living space.

- **a** Exterior—The exterior materials and proportions are visually subordinate and respectful of the historic homes character. Architectural detailing of the frieze, dormer and skirting are simplified versions of the original home.
 - I Windows and doors salvaged from demolition on the main house were incorporated in the new building. All new windows and doors are of wood construction and similar proportions to the originals.
 - ii The siding is a smooth finish lap siding hardi board.
 - **iii** The galvalume hipped standing seam roof and hipped dormer materials match the new roofing addition on the main house.
 - iv A simple exterior stair with steel railing accesses the 2nd floor living space.
 - V The two garage doors are similar proportions to those traditionally found in the neighborhood.

3 MAINTENANCE (PRESERVATION, RESTORATION, AND RECONSTRUCTION)

- **a** Exterior— Careful attention was paid to preserve the longevity and maintain the original character of the historic home.
 - 1 Windows —Preserved historic windows and reapplied glazing putty as needed.
 - **li** Shutters Preserved historic window shutters when applicable. Replaced missing shutters with new shutters to that match existing.
 - iii Siding Replaced rotten wood siding with matching profile siding.
 - Balconies Preserved historic architectural detailing around front and side balconies. Replaced rotten wood deck, balusters and railing to match existing.
 - Gutters Replaced all existing gutters and downspouts.
 - vi Front fence Replaced existing front fence with new fence replicated to match.
 - vii Paint Entire building was repainted with siding and trim colors to match existing.

Edward Diaz Construction, LLC 446 Queen Anne Ct San Antonio, TX. 78209

Construction Schedule for 119 Adams St. 4/9/2018

Note: The official amended start date was 3/2/2018. The contract states the duration of project as 395 days. The most recent change order has added 7 days to the project with extra labor and site meetings/delays due to a reexamination of foundation/framing, etc.

As of this updated schedule, the date of substantial completion would be 4/9/2019 – exactly 365 days from today. It is my sincere hope that we will reach project completion before this date by 60 days or more. However, due to the level of detail and possibility for delays and complications, this current schedule could easily take 4 to 6 weeks longer. This would still be within the time frame.

Completed to Date:

General Site work and protection. Removal of Pecan Tree. Demolition complete. Framing of Master Bedroom/Bath walls, Bath 02 walls, Bath 01. Perimeter frame of Mud Room built. Ceiling above kitchen LVLs and additional 2x12s installed. Window framing in Kitchen North & West walls, M. bath west wall, Utility room.

Change Order for Living Room floor framing & Plumbing at Bath 01 west wall (demoed wall) approved. Foundation footings for 15 piers including some extra to accommodate C.O.#1 excavated. Inspected by Moises Cruz on 4/6.

April 9 – end of month

Complete piers and complete C.O.#1, Continue framing at Main House. Install steel beams and headers, living room walls, floor framing above living room, M. Bed walls and M. porch framing. At Carriage House, form survey by Greaves.

Form for Carriage House foundation. Rough-in plumbing at C.H. Install three AC line sets in C.H. form. Trench and install Electrical service line for C.H.

May

Roof framing at Main House. Complete foundation at C.H. and begin framing. Goal is to be ready for Framing/Sheathing inspections at Main House and C.H. by end of May, early June. Rough-In plumbing and Electrical begin.

June

HVAC rough-ins, complete Plumbing & Electrical Rough-ins. Roofing at Main House and C.H. TPO at M. Bed porch. Tyvek wrap, flash, and install windows/doors. Porch foundation and beams completed. Exterior siding, soffits, etc. at C.H. and Main House. Also in June we should measure for Millwork and try and get this started. Insulation by end of month. Partial electrical inspection for later work at porch.

July

Drywall and continue work on exterior. Begin work at Porch. Painting at exteriors of C.H. and Main House at west wall, mud room, living room & M. porch. Garage Doors installed.

August

Complete Porch and polygal roof. Floor patching and install, interior trim work, install cabinetry. Tile work. Begin Painting at interior.

September

Trim Carpentry continued, Countertops installed, plumbing and lighting fixtures trimmed out. Fence.

October/November/December -

Complete interior detailing, Glass & Mirrors. Hardware install. Sand & finish floors, etc. Exterior work on Main House. Punch-listing, etc.

January 2019

Re grade driveway, general site clean-up, Painting, Punch-listing.

Feb 2019

Complete project.

Actual Date of Substantial Completion according to Contract, adding for C.O.#1: April 9, 2019